



LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (County)

Located in: Farmington Corner Code # Township

- 1. Public Land Survey T 1N R 9E M-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

MISCELLANEOUS RECORDING \$ 2.00 REMONUMENTATION 18 DEC 96 1:39 P.M. RECEIPT# 358 PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

APPROVED ON: 10-29-96 TS OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Randy Kolehouse, in a field survey on September 2, 1996, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13 containing numerical values for survey points.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-7 1817 Wampler G.L.O. Set Post (T1N, R10E)
1939 Baldwin County Surveyor's Notes Book 35-43 Iron Pipe
1987 Gorman L.C.R.C. L. 10295 P. 551 1" Iron in Monument Box

Records indicate this corner is common with A-7, T1N, R10E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 Found a 1-1/2" iron bar in a monument box at the C/L intersection of Inkster Road running North and South and 11 Mile Road running East and West per L.C.R.C. L. 10295 P. 551. This corner checks closely the distance South to M-8 per Baldwin's survey of 1939 and West to L-7 per the Lincolnshire and Churchill Estate Subdivisions.

- L.C.R.C. L. 10295 P. 551 1987
N 60° E 73.45' Nail & MDOT Cap in Lt. Pole
S 35° E 73.28' Nail & MDOT Cap in Lt. Pole
S 65° W 91.10' Chiseled "X" Rim of Manhole
N 35° W 66.80' Chiseled "X" in Rim of Manhole

Measure South 2641.60' to M-8 (G.L.O. = 2640.0') (Churchill Est. = 2641.69') (Calc. - Baldwin 1939 = 2643.3')
Measure West 2638.82' to L-7 (G.L.O. = 2625.48') (Baldwin 1939 - 2631.2') (Churchill Est. & Lincolnshire Sub. = 2639.6±')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 Replaced the 1-1/2" iron bar with a 5/8" x 24" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in an existing monument box.

- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side P. Pole N 56° E 73.46'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side P. Pole S 34° E 73.31'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side P. Pole S 56° W 82.12'
SE Cor. Conc. Pad to Lift Station Riser N 42° W 80.66'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/10/96
EARTH TECH
Surveyor's Michigan License No. 25854

