

**SURVEY & REMONUMENTATION**

LIBER 16843 PG 791

DEC 18 96 305731

MAY 22 1997

**LAND CORNER RECORDATION CERTIFICATE # 7.00 MISCELLANEOUS RECORDING**  
**Filing Requirement of Act 74, Mich. P.A. 1970 § 2.00 REMONUMENTATION**

For corners in **COMMISSION**

18 DEC 96 1:39 P.M. RECEIPT# 358  
 PAID RECORDED - OAKLAND COUNTY  
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Oakland (County) Located in: Farmington Corner Code #  
 Township

- |                                    |             |             |            |
|------------------------------------|-------------|-------------|------------|
| 1. Public Land Survey              | T <u>1N</u> | R <u>9E</u> | <u>M-8</u> |
|                                    | T _____     | R _____     | _____      |
|                                    | T _____     | R _____     | _____      |
|                                    | T _____     | R _____     | _____      |
| 2. Property Controlling in Section | S _____     | T _____     | R _____    |
|                                    | S _____     | T _____     | R _____    |
| 3. Miscellaneous Property in Sec.  | S _____     | T _____     | R _____    |
|                                    | S _____     | T _____     | R _____    |

Compliance with ACT 345, P.A. 1990  
 APPROVED ON: 10-26-96 TS  
 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on September 2 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-8	1817	Wampler	G.L.O.	Set Post (T1N, R10E)
	1966	N/A	Churchill Estates L. 121 P. 34	N/A
	1967	Postiff	Plat L. 121 P. 34	Monument
	1980	Kohn	L.C.R.C. L. 7732 P. 741	PK Nail

Records indicate this corner is common with A-8, T1N, R10E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 P.K. nail shown in L.C.R.C. L. 7732 P. 741 has been destroyed. Reset corner on the South line of Churchill Estates (L. 121 P. 34) 60.0' East of a concrete plat monument at the Southeast corner of Lot 99 of said subdivision. This point checks the two remaining witnesses from L.C.R.C. L. 7732 P. 741. Checks distance North to M-7 per Churchill Estates L. 121 P. 34 (1966).

L.C.R.C. L. 7732 P. 741 (1980)  
 12" Ash S 30° W 107.19' (m. 107.49')  
 U. Pole N 85° W 59.45' (m. 59.53')

Measure North 2641.60' to M-7 (G.L.O. = 2640.0') (Churchill Estates = 2641.69')  
 Measure South 2635.90' to M-9 (G.L.O. = 2640.0')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 Set a 5/8" x 24" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854." Also set a monument box.

- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side 11" Elm N 68° E 49.55'
- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in S Side P. Pole N 86° E 31.6'
- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side 8" Ash S 35° E 48.03'
- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side 14" Ash S 23° W 107.49'
- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in S Side P. Pole N 80° W 59.53'
- Plat Monument N 90° W 60.00'

7.00 FILE  
 2.00

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/10/96  
 EARTH TECH  
 Surveyor's Michigan License No. 25854

