

MAY 22 1997
OAKLAND COUNTY ROAD COMMISSION

NUMBER 16848 PG 792

LAND CORNER RECORDATION CERTIFICATE \$ 7.00 MISCELLANEOUS RECORDING
Filing Requirement of Act 74, Mich. P.A. 1970 \$ 2.00 REMONUMENTATION

For corners in

Oakland
(County)

Located in: Farmington Corner Code #
Township

18 DEC 96 1:39 P.M. RECEIPT# 358
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

- 1. Public Land Survey T 1N R 9E M-9
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 10-29-96-TS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Randy Kolehouse, in a field survey on August 5 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-9	1817	Wampler	G.L.O.	Set Post
	1946	N/A	Woodbine Sub. L. 58 P. 2	N/A
	1956	N/A	Kennedy's Park L. 83 P. 28	N/A
	N/A	N/A	Oakland County Road Commission Notes	N/A
	1981	Papke	Cert. Survey	N/A
	1981	Papke	L.C.R.C. L. 8029 P. 554	PK & 1/2" Iron

Records indicate this corner is common with A-9, T1N, R10E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 Found a railroad spike 1.4' West of the const. C/L of Inkster Road running North and South and 1.9' North of the const. C/L of 10 Mile Road running East and West per Oakland County Road Commission notes and L.C.R.C. L. 8029 P. 554.

L.C.R.C. L. 8029 P. 554 (1981)
PK in D.E. Pole S 30° E 79.21' (m. 79.16')

Measure West 2632.92' to L-9 (G.L.O. = 2623.17')
Measure South 2654.53' to M-10 (G.L.O. = 2640.0')
Measure North 2635.90' to M-8 (G.L.O. = 2640.0')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 Replaced railroad spike with a 5/8" x 24" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854." Also set a monument box.

Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side P. Pole N 32° W 43.96'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side P. Pole S 60° W 55.36'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side P. Pole S 30° W 79.37'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side N 54° E 53.74'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/10/96
EARTH TECH

Surveyor's Michigan License No. 25854

