

MAY 2-2 1997 COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING \$ 2.00 REMONUMENTATION 18 DEC 96 1:40 P.M. RECEIPT# 358 PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

Oakland (County)

Located in: Farmington Corner Code # Township

- 1. Public Land Survey T 1N R 9E M-10
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990 APPROVED ON: 10-26-96 TS OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on September 2, 1996, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 2-13 containing numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration:

M-10 1817 Wampler G.L.O. Set Post (T1N, R10E) 1978 Cantrell L.C.R.C. L. 7252 P. 519 5/8" Iron Pipe

Records indicate this corner is common with A-10, T1N, R10E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10 Found a 5/8" iron pipe 5.75' West of the C/L of Inkster Road running North and South and 60.18' West of concrete monument per L.C.R.C. L. 7252 P. 520. Per note on L.C.R.C. L. 7252 P. 519, this corner was also used by Spalding DeDecker & Associates in 1964 and checks the East-West fence line position.

L.C.R.C. L. 7252 P. 520 (1978) Plat Mon. East 60.10' (m. 60.18') Twin 8" Hickory NE 45.23' (m. 45.8')

Measures North 2654.53" to M-9 (G.L.O. = 2640.0') Measure South 2636.95' to M-11 (G.L.O. = 2640.0')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner;

M-10 Replaced the 5/8" iron pipe with a 5/8" x 24" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854." Also set a monument box.

Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side 18" Locust N 14° W 54.79' Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side Twin 10" Hickory N 54° E 45.80' Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side 10" Pine S 32° E 62.69' Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side Twin 10" Elm S 46° W 42.65' 5/8" Pipe in Conc. Mon. East 60.18'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/10/96

EARTH TECH

Surveyor's Michigan License No. 25854

