

MAY 22 1997

COMMISSION

LIBER 16848 PG 794

Dec 18 96 305734

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
18 DEC 96 1:40 P.M. RECEIPT# 35B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

Oakland (County)

Located in: Farmington Corner Code # Township

- 1. Public Land Survey T 1N R 9E M-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Compliance with ACT 345, P.A. 1990
APPROVED ON: 10-26-96 JS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Randy Kolehouse, in a field survey on September 2, 1996, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13 containing numerical data.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with 4 columns: M-11, Description, G.L.O., and Set Post. Includes entries for Wampler, N/A, Russell, Roskelly, and Arbor Oaks Sub.

Records indicate this corner is common with A-11, T1N, R10E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Found a 1" iron pipe in a monument box at the C/L intersection of Inkster Road running North and South and 9 Mile Road running East and West per L.C.R.C. L. 14637 P. 807 which checks the distance West to L-11 per Arbor Oaks Sub. L. 233 P. 1-3 (1994).

- L.C.R.C. L. 14687 P. 807 (1994)
P.K. & tag #10705 in utility pole N. 60° E. 67.10
P.K. & tag #10705 in utility pole S. 30° E. 74.82
P.K. & tag #10705 in utility pole S. 30° W. 61.02
P.K. & tag #10705 in utility pole N. 20° W. 50.52

- Measure North 2636.95' to M-10 (G.L.O. = 2640.0')
Measure South 2656.09' to M-12 (G.L.O. = 2640.0') (1852 Survey = 2663.0')
Measure West 2633.74' to L-11 (G.L.O. = 2624.5') (Arbor Oaks Sub. = 2633.66')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Replaced the 1" iron with a 5/8" x 24" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in an existing monument box.

- Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side Util. Pole N 23° W 50.47'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side P. Pole N 61° E 67.01'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side P. Pole S 34° E 74.72'
Set PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side P. Pole S 41° W 61.00'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/10/96
EARTH TECH

Surveyor's Michigan License No. 25854

