


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

OAKLAND COUNTY
T 2N R 7E

DESCRIPTION OF CORNER E 1/4 POST SEC. 13
CORNER MONUMENT 1" IRON PIPE WITH BRASS TAG
DATE MONUMENT PLACED AND WITNESSED AUGUST 17, 1961
WITNESSES TO CORNER..... GUARD POST W/STAKE N 17°30'E 63.81'



GUARD POST W/STAKE N 16°15'E 63.85'

20' CMP UNDER WIXOM RD (NORTH CMP) S 10°45'E 126.15'
AND
2 CHISELED NOTCHES IN END & A DIAGONAL MARK

20' CMP UNDER WIXOM RD S 11°30'W 126.45
AND
2 CHISELED NOTCHES IN END & A DIAGONAL MARK

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

THE SE & NE CORNERS OF SECTION 13 WERE RECOVERED FROM WITNESSES FURNISHED BY THE OAKLAND CO. RD. COMM., & A LINE WAS RUN BETWEEN THESE CORNERS AND NOTED APPROX. 10' OFF ROAD FILL AT ORIGINAL 1/4 POST LOCATION. THE ORIGINAL G.L.O. 1/4 POST WAS SET AT 40.00 CHAINS & MILE SET AT 80.00 CHAINS. THE NEW POST WAS SET AT THE MID POINT OF THE LINE BETWEEN THE SE & NE CORNERS. IT IS ASSUMED THAT THE NEW 1/4 POST IS OVER THE ORIGINAL LOCATION.

SURVEYOR'S SEAL.

SIGNED R. J. [Signature] DATE 1962
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing