

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 2. NR. 7E.

Date August 18, 1961 Oakland COUNTY

DESCRIPTION OF CORNER N 4 post Sec 13

DESCRIPTION OF CORNER MONUMENT 1" iron pipe w/ brass cap approximately 3" below the road

WITNESSES TO CORNER Power Pole N 71° 15' W 109.08' Horizontal Spike in E side Grade

Power Pole N 85° 30' E 45.40' Horiz. Spike & brass tag stamped "12029" in SW side.

Power Pole N 10° 30' E 159.60' Horiz spike in SW side.

1/2" Iron Pipe S 00° 30' W 32.90'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This point was re-established through information obtained from the Oakland County Road Commission. The old witnesses were used to locate the old point, and the new point, 1" iron pipe with a brass cap was set and new witnesses established.

SURVEYORS SEAL

SIGNED _____ DATE _____
REGISTERED LAND SURVEYOR