

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 21028 PAGE 439
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
01/27/2000 08:21:20 A.M. RECEIPT# 6667
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

Oakland (County) Located in: Corner Code #

- 1. Public Land Survey T2N R 7E A-1
- 2. Property Controlling in Section S T R SURVEY & REMONUMENTATION
- 3. Miscellaneous Property in Sec. S T R MAR 21 2000

Compliance with ACT 345, P.A. 1990
APPROVED ON: 8-18-99 JK
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SECTION

I, Grant J. Ward, R.L.S., in a field survey on August 11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
A-1 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-1 Northwest Corner of Section 6, T. 2 N., R. 7 E. Found Iron Pipe and Livingston County Remonumentation Cap #35999.

Previously Unrecorded.

This corner location is accepted by the Contractor and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-1 North 22.26' Set 60d Nail & Remonumentation Disc in East face of 12" Cherry.
- N 60° E 5.33' Set 60d Nail & Remonumentation Disc in South face of 10" Elm.
- S 85° W 15.65' Set 60d Nail & Remonumentation Disc in North face of 20" Elm.
- N 20° W 8.14' Set 60d Nail & Remonumentation Disc in East face of 8" Cherry.



Signed by _____
Surveyor's Michigan License No. 22445

Date August 16, 1999

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

2p
R.

JULY 20, 1999

Corner Code: A-1

DOSSIER FOR: THE NORTHWEST CORNER OF SECTION 6 (TOWNSHIP CORNER), MILFORD TOWNSHIP, T 2 N, R 7 E, OAKLAND COUNTY, MICHIGAN. Prepared under contract with the County of Oakland Under Act 345 of the Public Acts of 1990.

HISTORY:

This Corner has been accepted and used since before 1987 as witnessed by the Raymond J. Kostecke, Surveyor but it has not been previously recorded. This Corner is common to four Townships.

COLLATERAL EVIDENCE:

We found an iron pipe and remonumentation cap #35999 in place of the iron referred to in Mr. Kostecke's survey. This Corner lies 6 feet North of the South edge of a swamp. We measured 0.05 feet more than the recorded distance to the West 1/4 Corner of Section 6. We searched at least 50 feet in each direction for other stakes and found none that might represent the Corner.

SURVEYOR'S RECOMMENDATIONS:

This corner location is accepted by the Contractor and is generally accepted by Professional Surveyors as the best available evidence of the position of the original Corner. Therefore, I recommend that the Peer Review Group accept this Corner as monumented, with the references as shown on the enclosed form prepared according to Act 74 of the Public Acts of 1970.

Grant J. Ward, R.L.S.
License No. 22445

**SURVEY &
REMONUMENTATION**

MAR 21 2000

SECTION