

*Milford*  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

25837

For corners in

Oakland

(County)

Located In:

Corner Code #

1. Public Land Survey

T2N R 7E A-5

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

**SURVEY & REMONUMENTATION**

**MAR 21 2000**

LIBER 21028 PAGE 447  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
01/27/2000 08:21:21 A.M. RECEIPT# 6667  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 8-31-99 JK  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**SECTION**

I, Grant J. Ward, R.L.S., in a field survey on July 29, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
A-5 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
A-5 Northwest Corner of Section 18, T. 2 N., R. 7 E.

Previously Unrecorded.

This corner location is a careful and faithful re-establishment of the position of the original corner.

*2p  
R.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:



- A-5 Set 5/8" Iron Rod and Remonumentation Cap.
- N 40° E 25.07' Set MAG Nail & Remonumentation Disc in West face of 18" Oak.
- N 75° E 19.14' Set MAG Nail & Remonumentation Disc in North face of 24" Oak.
- S 50° W 58.37' Set MAG Nail & Remonumentation Disc in North face of Utility Pole.
- N 35° W 29.53' Set MAG Nail & Remonumentation Disc in South face of Utility Pole.
- South 21.78' Southeast Corner of Sec. 12, T. 2 N., R. 6 E.

Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 22445

Date August 2, 1999

July 20, 1999

Corner Code: A-5

DOSSIER FOR: THE SOUTHWEST CORNER OF SECTION 7, MILFORD TOWNSHIP,  
T 2 N, R 7 E, OAKLAND COUNTY, MICHIGAN. Prepared under contract with the  
County of Oakland Under Act 345 of the Public Acts of 1990.

**HISTORY:**

The original GLO notes call for this Corner to be 21.78 feet North of the Southeast Corner of Section 12 of Brighton Township. The 1954 survey by Warner and Warner for General Motors Corporation called for this Corner to be common. This Corner has not been previously recorded.

**COLLATERAL EVIDENCE:**

We set a 5/8 iron rod and remonumentation cap 21.78 feet North of the Corner for Brighton Township and on the Township Line as called for by the GLO notes and the Government Instructions for setting a Lost Corner. We did not set a concrete monument due to buried debris. This Corner lies 59.65 feet Southeasterly of Building No. 36, 1 foot West of the East edge of a gravel road (Darlington Hill Drive) and 10 feet North of a gravel drive to the East. Our measurements from the Corner for Brighton Township agrees with the recorded distances to the adjacent Corners to the North and South within 0.2 feet. We searched at least 50 feet in each direction for other stakes and found none that might represent the Corner.

**SURVEYOR'S RECOMMENDATIONS:**

This corner location is a careful and faithful re-establishment of the position of the original Corner. Therefore, I recommend that the Peer Review Group accept this Corner as monumented, with the references as shown on the enclosed form prepared according to Act 74 of the Public Acts of 1970.

---

Grant J. Ward, R.L.S.  
License No. 22445

**SURVEY &  
REMONUMENTATION**

**MAR 21 2000**

**SECTION**