

Milford  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

25846

LIBER 21028 PAGE 465  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
01/27/2000 08:21:22 A.M. RECEIPT# 6667  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

Oakland

(County)

Located In:

Corner Code #

1. Public Land Survey

T2N R 7E B-3

T R

T R

T R

2. Property Controlling in Section

S T SURVEY & REMONUMENTATION

3. Miscellaneous Property in Sec.

S T R MAR 21 2000

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 8-18-99 JK  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION

5. Private Claims \_\_\_\_\_

I, Grant J. Ward, R.L.S., in a field survey on July 29, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3		7		8		9		10		11		12	
4		18		17		16		15		14		13	
5													
6													
7													
8													
9													
10		30		29		28		27		26		25	
11													
12													
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
B-3 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
B-3 South 1/4 Corner of Section 6, T. 2 N., R. 7 E.

Previously Unrecorded.

This corner location is a careful and faithful re-establishment of the position of the original corner.

2p  
R

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-3 Set 5/8" Iron Rod and Remonumentation Cap.
- N 50° E 17.07' Set MAG Nail & Remonumentation Disc in Northwest face of 6" Ash.
- S 85° E 32.00' Set MAG Nail & Remonumentation Disc in North face of 16" Oak.
- N 80° W 57.78' Set MAG Nail & Remonumentation Disc in South face of 12" Elm.
- N 55° W 53.10' Set MAG Nail & Remonumentation Disc in South face 16" Ash.



Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 22445

Date August 2, 1999

JULY 20, 1999

Corner Code: B-3

DOSSIER FOR: THE SOUTH 1/4 CORNER OF SECTION 6, MILFORD TOWNSHIP, T 2 N, R 7 E, OAKLAND COUNTY, MICHIGAN. Prepared under contract with the County of Oakland Under Act 345 of the Public Acts of 1990.

**HISTORY:**

The only information that might have been available for this Corner from the time it was originally set would have been from the Warner and Warner General Motors Corporation survey in 1954, but it was not shown at that time. This Corner has not been previously recorded.

**COLLATERAL EVIDENCE:**

We set a 5/8" iron rod and remonumentation cap on line and by single proportion measurement between the Southeast and the Southwest Corners of Section 6 per the Government instructions to set a Lost Corner. We didn't set a concrete monument due to buried debris. We measured 0.89 feet longer than the distance shown on the Warner and Warner survey for the South Line of Section 6. We searched at least 50 feet in each direction for other stakes and found none that might represent the Corner.

**SURVEYOR'S RECOMMENDATIONS:**

This corner location is a careful and faithful re-establishment of the position of the original Corner. Therefore, I recommend that the Peer Review Group accept this Corner as monumented, with the references as shown on the enclosed form prepared according to Act 74 of the Public Acts of 1970.

---

Grant J. Ward, R.L.S.  
License No. 22445

SURVEY &  
REMONUMENTATION

MAR 21 2000

SECTION