

AUGUST 29, 1999

Corner Code: B-9

DOSSIER FOR: THE SOUTH 1/4 CORNER OF SECTION 19, MILFORD TOWNSHIP,
T 2 N, R 7 E, OAKLAND COUNTY, MICHIGAN. Prepared under contract with the
County of Oakland Under Act 345 of the Public Acts of 1990.

HISTORY:

This Corner has been accepted and used since before 1963 as witnessed by the Road Commission for Oakland County at that time. It was recorded under Act 74 of the Public Acts of 1970 in Liber 11603, Page 670, by Gilbert G. Bonno, Surveyor in 1989.

COLLATERAL EVIDENCE:

We found a 1/2" iron rod and set a 5/8" iron rod and remonumentation cap in its place. This Corner lies on the Centerline of Buno Road on line with a fence line to the South and a tree row to the North. We found an iron pipe 32.78 feet to the North and an iron rod and cap #19005 33.48 feet to the South. We measured 0.11 feet less and 0.52 feet more than the recorded distances to the Northwest and the Northeast Corners of Section 30. We searched at least 50 feet in each direction for other stakes that might represent the Corner.

SURVEYOR'S RECOMMENDATIONS:

This corner location is accepted by the Contractor and is generally accepted by Professional Surveyors as the best available evidence of the position of the original Corner. Therefore, I recommend that the Peer Review Group accept this Corner as monumented (while considering the other iron found near this location) with the references as shown on the enclosed form prepared according to Act 74 of the Public Acts of 1970.

Grant J. Ward, R.L.S.
License No. 22445

SURVEY &
REMONUMENTATION

MAR 21 2000

SECTION