

*M. Ward*

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

25863

LIBER 21028 PAGE 499  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
01/27/2000 08:21:22 A.M. RECEIPT# 6667  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

Oakland  
(County)

Located In:

Corner Code #

1. Public Land Survey

T2N R 7E D-3

T R

T R

T R

S T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

SURVEY &  
REMONUMENTATION

MAR 21 2000

SECTION

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 7-28-99 JIL  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Grant J. Ward, R.L.S., in a field survey on July 19, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	I
1													
2		6		5		4		3		2		1	
3				•									
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-3 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-3 North 1/4 Corner of Section 8, T. 2 N., R. 7 E.

Previously Unrecorded.

This corner location is a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-3 Set Reference Monument and Remonumentation Cap 386' East on line with E-3.
- N 65° E 36.19' Set 60d Nail & Remonumentation Disc in Northwest face of 10" Oak.
- East 13.60' Set 60d Nail & Remonumentation Disc in Southwest face of 14" Cherry.
- S 35° E 48.08' Set 60d Nail & Remonumentation Disc in West face of 24" Maple.
- N 20° W 83.10' Set 60d Nail & Remonumentation Disc in East face of 12" Poplar.



Signed by \_\_\_\_\_

Date July 27, 1999

Surveyor's Michigan License No. 22445

JULY 10, 1999

Corner Code: D-3

DOSSIER FOR: THE SOUTH 1/4 CORNER OF SECTION 5, MILFORD TOWNSHIP, T 2 N, R 7 E, OAKLAND COUNTY, MICHIGAN. Prepared under contract with the County of Oakland Under Act 345 of the Public Acts of 1990.

HISTORY:

This Corner has been accepted and used since before 1993, as evidenced by an un-recorded survey by Boss Engineering, Gary R. Boss, Surveyor. This point was originally set by the G.L.O. in the lake. Mr. Boss determined this point to be midway and on line between the Southwest and the Southeast Corners of Section 5. This point has not been previously recorded.

COLLATERAL EVIDENCE:

We set a reference concrete monument and remonumentation cap 386.00 feet East of the Corner on line with the Southeast Corner of Section 5. The Corner location was calculated to be midway and on line between the adjacent Section Corners per the Government Instructions for setting a Lost or Obliterated Corner. We measured 0.02 feet more than the distance reported by Mr. Boss for the entire mile.

SURVEYOR'S RECOMMENDATIONS:

This corner location is a careful and faithful re-establishment of the position of the original Corner. Therefore, I recommend that the Peer Review Group accept this Corner as monumented, with the references as shown on the enclosed form prepared according to Act 74 of the Public Acts of 1970.

---

Grant J. Ward, R.L.S.  
License No. 22445

SURVEY &  
REMONUMENTATION

MAR 21 2000

SECTION