

SURVEY & REMONUMENTATION

PT. 11/18/00
MAY 24 2000

LIBER 21143 059

58658

LAND CORNER RECORDATION CERTIFICATE LIBER 21143 PAGE 59
Filing Requirement of Act 74, Mich. P.A. 1970

\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/28/2000 01:52:10 P.M. RECEIPT# 16297
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

SECTION

For corners in

Oakland	Located In:	Corner Code #
(County)		
1. Public Land Survey	T2N R 7E	D-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-7-99 JK
OAKLAND COUNTY REMONUMENTATION PEER REVIEW COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Grant J. Ward, R.L.S., in a field survey on October 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
D-13 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
D-13 South 1/4 Corner of Section 32, T. 2 N., R. 7 E. Found Monument.

Previously unrecorded.

This corner location of a corner is accepted by the Contractor and is generally accepted by Professional Surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:



- D-13 North 4.98' Set Remonumentation Cap on Existing Monument.
- Set 60d Nail & Remonumentation Disc in East face of 12" Oak.
- N 45° E 24.13' Set 60d Nail & Remonumentation Disc in Southeast face of Twin 10"-8" Oak.
- S 80° E 36.95' Set 60d Nail & Remonumentation Disc in South face of 12" Oak.
- N 80° W 23.52' Set 60d Nail & Remonumentation Disc in South face of 6" Oak.
- S 85° W 236.47' Found Monument & Remonumentation Cap, North 1/4 Corner, Section 5, T. 1 N., R. 7 E.
- N 85° E 107.96' Found Monument.

Signed by _____
Surveyor's Michigan License No. 22445

Date October 22, 1999