

LIBER 21028 535
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1974

25881

For corners in

Oakland
 (County)

Located in:

Corner Code #

1. Public Land Survey

T2N R 7E F-5

2. Property Controlling
 in Section

S T R
 S T R

**SURVEY &
 REMONUMENTATION**

3. Miscellaneous
 Property in Sec.

S T R
 S T R

MAR 21 2000

LIBER 21028 PAGE 535
 \$3.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 01/27/2000 08:21:22 A.M. RECEIPT# 6667
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 9-29-99 JK
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

SECTION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Grant J. Ward, R.L.S., in a field survey on August 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 F-5 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 F-5 North 1/4 Corner of Section-16, T. 2 N., R. 7 E.

Previously Unrecorded.

This corner location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-5 Set 5/8" Iron Rod and Remonumentation Cap in a New Monument Box 1' South of Centerline of General Motors Road.
- N 50° E 74.71' Set MAG Nail & Remonumentation Disc in Northwest face of 8" Crab Apple.
- S 10° E 41.09' Set MAG Nail & Remonumentation Disc in East face of 12" Locust.
- N 50° W 52.52' Set MAG Nail & Remonumentation Disc in Northeast face of Utility Pole.
- N 15° W 45.42' Set MAG Nail & Remonumentation Disc in Northwest face of 12" Crab Apple Cluster.



Signed by [Signature]
 Surveyor's Michigan License No. 22445

Date September 19, 1999

SEPTEMBER 19, 1999

Corner Code: F-5

DOSSIER FOR: THE SOUTH 1/4 CORNER OF SECTION 9, MILFORD TOWNSHIP, T 2 N, R 7 E, OAKLAND COUNTY, MICHIGAN. Prepared under contract with the County of Oakland Under Act 345 of the Public Acts of 1990.

HISTORY:

This Corner has been accepted and used since the early 1950s, as evidenced by a coordinate traverse sheet from Camp Dearborn. This Corner has not been previously recorded.

COLLATERAL EVIDENCE:

We set a 5/8" iron rod and remonumentation cap in a new monument box 1 foot South of the Centerline of General Motors Road, 41 feet South of a fence line on a tree row to the West. There is no evidence of occupation to the North or South from the Corner. The distances we measured around Section 9 agreed with the record from the Camp Dearborn survey within between 0.2 feet to 1.0 feet generally. We found nothing at this Corner, so we set it based on the recorded Camp Dearborn angle and distance from the Southeast Corner of the Section using the East 1/4 Corner as a backsight. We found an iron rod and cap #12584 1326 feet West of the Corner and 31.08 feet South of the Section Line and a concrete monument 59.03 feet South of the Section Line 2574 feet West of the Corner, which would indicate a kink in the Section Line or less likely that this Corner should be 4 feet South of the Camp Dearborn position.

SURVEYOR'S RECOMMENDATIONS:

This corner location is accepted by the Contractor and is generally accepted by Professional Surveyors as the best available evidence of the position of the original Corner. Therefore, I recommend that the Peer Review Group accept this Corner as monumented, with the references as shown on the enclosed form prepared according to Act 74 of the Public Acts of 1970.

Grant J. Ward, R.L.S.
License No. 22445

SURVEY &
REMONUMENTATION

MAR 21 2000

SECTION