

SEPTEMBER 19, 1999

Corner Code: F-11

DOSSIER FOR: THE SOUTH 1/4 CORNER OF SECTION 28, MILFORD TOWNSHIP,
T 2 N, R 7 E, OAKLAND COUNTY, MICHIGAN. Prepared under contract with the
County of Oakland Under Act 345 of the Public Acts of 1990.

HISTORY:

This Corner has been accepted and used since before 1934 as witnessed by the Road Commission for Oakland County at that time. This Corner has not been previously recorded.

COLLATERAL EVIDENCE:

We found a bent 5/8" iron rod and set a 5/8" iron rod and and remonumentation cap in its place. This Corner lies 4 feet North of the Centerline of Maple Road (gravel). There are fence corners 33 feet North and 33 feet South of the Corner. We found a concrete monument 32.97 feet North of the Corner. We measured 1.62 feet less than the recorded distance to the Southwest Corner of Section 28 per the HCMA survey. We searched at least 50 feet in each direction for other stakes and found none that might represent the Corner.

SURVEYOR'S RECOMMENDATIONS:

This corner location is accepted by the Contractor and is generally accepted by Professional Surveyors as the best available evidence of the position of the original Corner. Therefore, I recommend that the Peer Review Group accept this Corner as monumented, with the references as shown on the enclosed form prepared according to Act 74 of the Public Acts of 1970.

Grant J. Ward, R.L.S.
License No. 22445

SURVEY &
REMONUMENTATION

MAR 21 2000

SECTION