

LIBER 21028 547
W. Ward

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

25887

For corners in

Oakland
 (County)

Located in: Corner Code #

1. Public Land Survey T2N R 7E G-3
 T R
 T R
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

**SURVEY &
 REMONUMENTATION**
 MAR 21 2000

LIBER 21028 PAGE 547
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 01/27/2000 08:21:22 A.M. RECEIPT# 6667
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEE.

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 7-14-99 JK
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Num

SECTION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Grant J. Ward, R.L.S., in a field survey on June 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K
2	6			5			4		3		2
3											
4	7				8		9		10		11
5											
6	18			17		16		15		14	
7											
8	19			20		21		22		23	
9											
10	30			29		28		27		26	
11											
12	31			32		33		34		35	
13											

A. Description of original monument and accessories and/or subsequent restoration:

G-3 Post, per G.L.O. Notes.

*2P
2*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-3 Northeast Corner of Section 9, T. 2 N., R. 7 E. Found 1/2" Iron Rod.

Previously Recorded in L. 6405 P. 386 (1) and L. 12432 P. 335 (1) of Oakland County Records.

(n) Indicates the number of references that confirms this corner by dimensional tie.

This corner location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3 Set Monument and Remonumentation Cap.
 S 65° E 69.53' Set 60d Nail & Remonumentation Disc in South face of 12" Pine.
 S 25° W 33.12' Set 60d Nail & Remonumentation Disc in Top Steel Gate Post.
 S 55° W 32.30' Set 60d Nail & Remonumentation Disc in Top Steel Gate Post.
 N 05° W 22.37' Set 60d Nail & Remonumentation Disc in Southwest face of Utility Pole.



Signed by _____
 Surveyor's Michigan License No. 22445

Date July 12, 1999

JULY 3, 1999

Corner Code: G-3

DOSSIER FOR: THE SOUTHEAST CORNER OF SECTION 4, MILFORD TOWNSHIP, T 2 N, R 7 E, OAKLAND COUNTY, MICHIGAN. Prepared under contract with the County of Oakland Under Act 345 of the Public Acts of 1990.

HISTORY:

This Corner has been accepted and used since before 1974, as evidenced by recordings under Act 74 of the Public Acts of 1970, by Gary R. Stonerock, Surveyor as recorded in Liber 6405, Page 386.

COLLATERAL EVIDENCE:

This Corner lies 3 feet East of an electric transformer and 6 feet West of a chain link fence. We found a 1/2" iron rod and set a concrete monument with remonumentation cap in its place. We measured 0.02 feet more and 0.20 feet less than the recorded distances to the North and East 1/4 Section Corners of Section 9, respectively and 1.46 feet less than the recorded distance to the North 1/4 Corner of Section 10.

We searched at least 50 feet in each direction for other stakes and found none that might represent the Corner.

SURVEYOR'S RECOMMENDATIONS:

This corner location is accepted by the Contractor and is generally accepted by Professional Surveyors as the best available evidence of the position of the original Corner. Therefore, I recommend that the Peer Review Group accept this Corner as monumented, with the references as shown on the enclosed form prepared according to Act 74 of the Public Acts of 1970.

Grant J. Ward, R.L.S.
License No. 22445

SURVEY &
REMONUMENTATION

MAR 21 2000

SECTION