

SEPTEMBER 19, 1995

Corner Code: I-9

DOSSIER FOR: THE SOUTHEAST CORNER OF SECTION 22, MILFORD TOWNSHIP, T 2 N, R 7 E, OAKLAND COUNTY, MICHIGAN. Prepared under contract with the County of Oakland Under Act 345 of the Public Acts of 1990.

HISTORY:

This Township was originally surveyed by Joseph Wampler, Deputy Surveyor, in 1823.

SPECIAL NOTES:

After reviewing the transcripts of the Original GLO Notes, I believe that the original survey lines were run as documented and that the dimensions seem to be accurate in the Southeast 1/4 of this Township, with our measurements agreeing within 10 to 15 feet, in practically all instances.

This Corner has been accepted and used since before 1974, as evidenced by a recorded survey.

COLLATERAL EVIDENCE:

We found an iron pipe at the Centerline of the intersection of Buno and South Hill Roads. There are tree rows running North and South 24 feet West of the Corner and 24 feet East of the Corner. There are tree rows running West 24 feet North and 24 feet South of the Corner. There is a fence running West 24 feet North of the Corner. The Southwest corner of a fence is 24 feet North and 24 feet East of the Corner.

We searched at least 50 feet in each direction for other stakes and found none that might represent the Corner.

The measured dimensions to all four adjacent 1/4 Corners agree with the dimensions taken from recorded surveys, the most recent tax maps and/or other old surveys within one half of a foot.

This Corner was first recorded in 1974 by Kieft Engineering in Liber 6270, Page 255, of the Oakland County Records.

SURVEYOR'S RECOMMENDATIONS:

Therefore, I recommend that the Peer Review Group accept this Corner as monumented, with the references as shown on the enclosed form prepared according to Act 74 of the Public Acts of 1970.

Grant J. Ward, R.L.S.
License No. 22445