

COPY
COMMISSION

LIBER 1686091

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
26 DEC 96 9:24 A.M. RECEIPT# 7B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

| | | |
|---------------------------------------|-------------------------|---------------|
| _____ Oakland _____ (county) | Located In: | Corner Code # |
| 1. Public Land Survey | T 2N R 8E | C-7 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 12-04-96 TS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, James E. Kovas, in a field survey on December 4, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 10 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | ● | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-7
- 1816 - G.L.O. Set Corner
- 1954 - Ash Engineering, Survey, no monument description, no accessories, Distance: B-7 to C-7 = 2639.35'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 No monument or accessories found

Distance: C-5 to C-8 = 7920.00' (G.L.O.); 7916.85' (Wade-Trim)

C-7 was re-established by holding the distance along the North Section line (B-7 to C-7) from the Ash Survey and proportioning between G.L.O. corners (C-5 to C-8).

The resulting distances between corners is as follows: C-7 to B-7 = 2639.65' C-7 to C-5 = 5277.90'
C-7 to F-7 = 7957.16' C-7 to C-8 = 2638.95'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 Set Concrete Monument with Brass Oakland Co. Remon Cap# 33138, in Marsh

- WIT:
- North 3.0' Set yellow Carsonite Post "Survey Mark"
 - S50°W 121.10' Set 60d Nail/ Oakland Remon Brass Tag# 33138 NW Face 4" Tamarack
(Deer run by this witness tree running NE-SW)
 - S50°E 126.08' Set 60d Nail/ Oakland Remon Brass Tag# 33138 NE Face 4" Elm
(Deer run by this witness tree running NW-SE)



Signed by James E. Kovas Date December 20, 1996

Surveyor's Michigan License No. 33138