

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Oakland _____ Located In: _____ Corner Code # _____
 (county)

1. Public Land Survey T 2N R 8E _____ F-11 _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 26 DEC 96 9:25 A.M. RECEIPT# 78
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1970
 APPROVED ON: 10-21-96 Y3
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, James E. Kovas, in a field survey on November 25, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 F-11

1816 - G.L.O. Set 1/4 Post WIT: N31°W 28 Lks. W.Oak; S41-1/2°E 45 Lks. W.Oak; 1968 - "Highgate on the Green No.1" (Liber 125 Plats, Page 6) Accepted corner matches plat monumentation; 1993 - David P. Smith, LCRC (Liber 13429, Page 162) Concrete Monument WIT: N30°W 26.05' Nail/ Tag W.Face 30" Oak; N45°W 35.28' Nail/ Tag E.Face 30" Oak; N45°E 17.25' Nail/ Tag W.Face 12" Oak;

Distances: F-11 to E-11 = 2646.60' (GLO); 2641.13' (Wade-Trim)
 F-11 to G-11 = 2646.60' (GLO); 2650.23' (Wade-Trim)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11 Found Concrete Monument (Concrete Broken at Top)


WIT: N30°W 26.21' Fnd Nail/ Tag W.Face 30" Oak
 N45°W 35.29' Fnd Nail/ Tag E.Face 30" Oak
 N45°E 17.14' Fnd Nail/ Tag W.Face 12" Oak
 North (along E.Plat Bndry) 13.65' Fnd Plat Iron

The Concrete Monument found was ratified by the Peer Review Committee on November 25, 1996, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 Set New Concrete Monuent with Brass Oakland Co. Remonumentation Cap # 33138

WIT: N30°W 26.19' Set 60d Nail/ Oakland Co. Remon Tag# 33138 W.Face 22" R.Oak
 N70°E 29.94' Set 60d Nail/ Oakland Co. Remon Tag# 33138 N.Face 9" Cherry
 N70°W 35.29' Set 60d Nail/ Oakland Co. Remon Tag# 33138 S.Face 30" W.Oak
 South 17.74' Set 60d Nail/ Oakland Co. Remon Tag# 33138 W.Face 36" R.Oak
 South 17.5' East-West Fence Line (Broken Down)
 North 13.65' Fnd 3/4" Plat Iron



Signed by James E. Kovas Date December 20, 1996

Surveyor's Michigan License No. 33138

*700 File
200*