

MAY 16 1996

LIBER 15907 pg 742

DEC 27 95 257032

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland Located In: Commerce Twp. Corner Code #  
(County)

- 1. Public Land Survey T 2N R 8E G-2  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 12-07-95 T.S.  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, David Pawlaczyk, in a field survey on October 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1823 Post	G.L.O.	A. Holmes	N/A	Notes	\$ 7.00 MISCELLANEOUS RECORDING
					\$ 2.00 REMONUMENTATION
					27 DEC 95 9:59 A.M. RECEIPT# 54B
					PAID RECORDED - OAKLAND COUNTY
					LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A concrete monument in a field currently occupies this corner.

Field measurements were made between the following corners:

G-1 to G-2	2887.75	meas.
	2751.54	Rec. G.L.O.
G-2 to G-3	2667.36	meas.
	2640.00	Rec. G.L.O.
	2667.26	Rec. Condo No. 645
		Oakland County Records

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 2" diameter brass cap stamped "Oakland County Remonumentation PS 17632" on the existing found concrete monument

- N. 30° E. 27.94' P.K. Nail & O.C.R. tag W. face 36" Oak
- N. 80° E. 33.01' P.K. Nail & O.C.R. tag N. face 16" Oak
- S. 30° E. 35.35' P.K. Nail & O.C.R. tag W. face 16" Oak
- N. 78° W. 18.02' P.K. Nail & O.C.R. tag S. face 10" Oak

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]  
Surveyor's Michigan License No. 17632

Date 12-20-95

