

SURVEY & REMONUMENTATION

MAY - 1 1995

COMMISSION

For corners in Oakland

(County)

Commerce Twp.

Located In:

Corner Code #/

- | | | |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>2N</u> R <u>8E</u> | <u>G-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

I, David Pawlaczyk, in a field survey on December 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1815 Post	G.L.O.	A. Holmes	N/A	Notes
1984 Monument box	L.C.R.C.	E. Anderson	#11495	L8574 P496

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1/2" iron rod in an existing monument box in asphalt pavement currently occupies this corner. No ties were given from L.C.R.C. L8574 P496. A corner of a 4' chain link fence falls 57.0' south and 3.0' east of this monument box.

Field measurements were made between the following corners:

G-4 to F-4	2683.82	meas.		
G-4 to G-3	2643.77	meas.		
	2640.00	rec.	G.L.O.	Notes
G-4 to H-4	2625.15	meas.		

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 2" diameter brass cap stamped "Oakland County Remonumentation PS #17632" on an existing 1/2" iron rod in an existing monument box in asphalt pavement.

N.05° W.	46.65'	P.K. nail and O.C.R. tag W. face Twin 10" Oak
N.80° E.	145.25'	P.K. nail and O.C.R. tag N.W. face street light
S.32° E.	56.44'	P.K. nail and O.C.R. tag N.E. face clump 6" trees
Due S.	28.08'	P.K. nail O.C.R. tag N.E. face 30" Oak
S.30° W.	37.03'	P.K. nail and O.C.R. tag N.W. face 8" Oak

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]

Date 2-16-95

Surveyor's Michigan License No. 17632

Mar 10 95 040446

OK - T. SMITH

\$ 7.00 MISC RECORDING CHG - IN HOUSE
 2.00 REMON CHG - IN HOUSE
 MAR 95 4:05 P.M. RECEIPT# 1778
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990
 APPROVED ON: 12-03-94
 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

