

MAY 22 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

\_\_\_\_\_ Oakland \_\_\_\_\_ Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(county)

1. Public Land Survey T 2N R 8E \_\_\_\_\_ G-13 \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
26 DEC 96 9:26 A.M. RECEIPT# 7B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

APPROVED ON: 10-21-96 JS  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, James E. Kovas, in a field survey on November 25, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13  
1816 - G.L.O. Set Corner  
1961 - Oakland Co. Road Comm., Small Boat Spike 4" Deep WIT: North 38.80' 19" Oak; NW 75.68' 22" Oak; SE 23.21' 25" Elm; 1990 - Spaulding, DeDecker & Assoc. (Liber 11645, Page 213-215 & Liber 11645, Page 219), Found Iron WIT: N01°E 38.28' P.K. Nail/ SDA Tag W.Face 20" Oak; N53°W 76.03' P.K. Nail/ SDA Tag SW Face 20" Oak; S54°E 177.67' P.K. Nail NE Face U.Pole; S38°W 69.29' P.K. Nail/ SDA Tag W.Face U.Pole; West 321.84' Fnd P.K. Nail (NE Cor, Sec 4, T1N, R8E, Liber 6246, Page 586).  
Distances: G-13 to F-13 = 2640.00' (GLO); 2646.35' (Wade-Trim)  
G-13 to G-12 = 2640.00' (GLO); 2651.89' (Wade-Trim)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 Found 1/2" Iron Rod at bituminous road grade  
Found Small Boat Spike, 2.0' below bituminous grade, at same location as 1/2" Iron Rod.

WIT: N01°E 38.28' Fnd P.K. Nail/ SDA Tag W.Face 32" R.Oak  
N53°W 76.03' Fnd P.K. Nail/ SDA Tag SW Face 24" Oak  
S54°E 177.67' Fnd P.K. Nail/ SDA Tag NE Face U.Pole  
S38°W 69.29' Fnd P.K. Nail/ SDA Tag W.Face U.Pole  
West 321.84' Fnd P.K. Nail (NE Cor, Sec 4, T1N, R8E, Liber 6246, Page 586)

The location of the found 1/2" Iron Rod and Small boat spike was ratified by the Peer Review Committee on November 25, 1996, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 Set 3/4" Iron Rod with Brass Oakland Co. Remonumentation Cap# 33138 in New Monument Box, at the approved location.

WIT: North 38.24' Fnd Nail/ Tag# 8386 SDA W.Face 20" Oak  
N55°W 76.06' Set 60d Nail/ Oakland Co. Remon Tag# 33138 SW Face 24" Oak  
N35°W 119.66' Set 60d Nail/ Oakland Co. Remon Tag# 33138 SW Face 18" Oak  
N05°W 73.39' Set 60d Nail/ Oakland Co. Remon Tag# 33138 E.Face 32" R. Oak  
S30°E 88.98' Set 60d Nail/ Oakland Co. Remon Tag# 33138 NE Face 14" Pine  
S20°W 91.94' Set 60d Nail/ Oakland Co. Remon Tag# 33138 W.Face 10" Maple

Signed by James E. Kovas Date December 20, 1996

Surveyor's Michigan License No. 33138

