

SURVEY & REMONUMENTATION

MAY - 1 1995

COMMISSION

LIBER. 15288 PG 533

MAR 10 95 04 04 47

OK - T. SMITH

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISC RECORDING CHG - IN HOUSE
 \$ 2.00 REMON CHG - IN HOUSE
 10 MAR 95 4:06 P.M. RECEIPT# 177B
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in Oakland
 (County)

Located in: Commerce Twp. Corner Code #H-1

	2N	8E	H-1
1. Public Land Survey	T _____ R _____	T _____ R _____	_____
	T _____ R _____	T _____ R _____	_____
	T _____ R _____	T _____ R _____	_____
	T _____ R _____	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	S _____ T _____ R _____	_____
	S _____ T _____ R _____	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	S _____ T _____ R _____	_____
	S _____ T _____ R _____	S _____ T _____ R _____	_____

Compliance with ACT 345, P.A. 1990
 APPROVED ON: 12-27-94
 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David Pawlaczyk, in a field survey on December 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

No corner was set referencing original government land office notes.
 No L.C.R.C. was ever recorded for H-1, T-2-N., R-8-E.,
 No. L.C.R.C. was ever recorded for H-13, T-3-N., R-8-E.
 No falling was ever recorded on G.L.O. notes for H-13, H-1.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 3/4" iron rod in an existing monument box in asphalt pavement currently occupies this corner. This corner is on \pm centerline Bogie Lake Road extended north and \pm 260' west of the centerline Oxbow Road to the north. A bent "T" iron was found 33.0' S. and 33.5' E. at the base of old wood fence post.

Field measurements were made between the following 6 corners:

H-1 to I-1	2619.92	meas.		
H-1 to G-1	2547.41	meas.		
H-1 to H-2	2654.90	meas.		
	2654.43	rec.	Property desc.	Oakland County Planning

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 3/4" pipe in an existing monument box with a 5/8" x 24" iron rod with a 2" diameter brass cap stamped "Oakland County Remonumentation P.S. #17632".

N.40° E.	65.47'	P.K. nail and O.C.R. tag in N.W. face D.E. pole
S.21° E.	68.20'	P.K. Nail and O.C.R. tag N. face 6" Maple
S.18° W.	106.98'	P.K. nail and O.C.R. tag N.W. face D.E. pole
N.38° W.	29.80'	P.K. nail and O.C.R. tag N.E. face 20" Maple

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Date 2-16-95
 Surveyor's Michigan License No. 17632

