

SURVEY & REMONUMENTATION

MAY - 1 1995

LIBER **15288** PC **491**

MAR 10 95 040405

COMMISSION

LAND CORNER RECORDATION CERTIFICATE \$ 7.00 MISC RECORDING CHG - IN HOUSE
 Filing Requirement of Act 74, Mich. P.A. 1970 \$ 2.00 REMON CHG - IN HOUSE

For corners in Oakland

Commerce Twp.

Located In: _____ Corner Code # _____

10 MAR 95 3:59 P.M. RECEIPT# 177B
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-27-95
 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

OK - T. SMITH

Register of Deeds Stamp & File Number

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>2N</u> R <u>8E</u> | <u>I-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David Pawlaczyk, in a field survey on December 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

	1815 Post	G.L.O.	A. Homes	n/a	Notes
	1975 3/4" Iron	L.C.R.C.	E. Anderson	#11495	L6462 P886
	1978 1/2" Re-rod	Survey	D. Finney	#15536	L7659 P258
	1979 1/2" Iron	L.C.R.C.	D. Finney	#15536	L7580 P812

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 A 1/2" iron rod in existing asphalt pavement currently occupies this corner. The following witness ties were used to recover and verify its position:

3 ties match L.C.R.C. L7580 P812

Field measurements were made between the following corners:

I-2 to I-1	2886.45	meas.		
	2737.68	rec.	G.L.O.	Notes
	2885.17	rec.	Plats	L26 P4
I-2 to I-3	2641.31	meas.		
	2640.00	rec.	G.L.O.	Notes
	2642.53	rec.	Plats	L29 P1

7.00
2.00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1/2" iron rod in asphalt pavement with a 5/8" x 24" iron rod with a 2" diameter brass cap stamped "Oakland County Remonumentation P.S. #17632" with a new monument box.

N.35° W.	46.42'	P.K. nail and O.C.R. tag in S.W. face Twin 6" tree
S.70° E.	35.82'	P.K. nail and O.C.R. tag in S.W. face D.E. pole
S.30° E.	69.45'	P.K. nail and O.C.R. tag S.W. face 30" Maple
S.45° W.	42.33'	P.K. nail and O.C.R. tag N.W. face D.E. pole



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]

Date 2-16-95

Surveyor's Michigan License No. 17632