

**SURVEY &
REMONUMENTATION**

MAR 10 95 040407

LIBER. **15288** PG **493**

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Commerce Twp.

\$ 7.00 MISC RECORDING CHG - IN HOUSE
2.00 REMON CHG - IN HOUSE
MAR 95 3:59 P.M. RECEIPT# 1778
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in **COMMISSION**
Oakland

(County)	Located In:	Corner Code #/
	2N 8E	I-6
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 12-05-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
OK - T. SMITH
Register of Deeds Stamp & File Number

David Pawlaczyk October 24 94

I, _____, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1815 Post	G.L.O.	A. Holmes	N/A	Notes
1976 1/2" Re-rod	Survey	W. Carnahan	#13029	L8206 P182
1992 3/4" Pipe	Survey	R. Kostecke	#12584	L13378 P350
1993 1" Iron	L.C.R.C.	J. Kapelczak	#24598	L13682 P798
1993 3/4" Pipe	Survey	R. Kostecke	#12584	L13827 P679

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1" iron pipe 0.7' ± below top of asphalt pavement currently occupies this corner. The following ties were used to recover and verify its present position:

4 ties from L.C.R.C. L13682 P798

Field measurements were made between the following corners:

I-6 to I-5	2658.91	meas.		
	2640.00	rec.	G.L.O.	Notes
	2658.89	rec.	Plats	L215 P12-16
I-6 to I-7	2634.69	meas.		
	2640.00	rec.	G.L.O.	Notes
	2634.75	rec.	Survey	L13378 P350
	2634.94	rec.	Plats	L226 P19
I-6 to J-6	2619.07	meas.		

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1" iron pipe with a 5/8" x 24" iron rod with a 2" diameter brass disk stamped "Oakland County Remonumentation P.S. #17632" with a new monument box in asphalt pavement.

N.40° W.	59.62'	P.K. nail and O.C.R. tag N.E. face 16" Maple
S.89° E.	55.76'	Found State of Michigan concrete mon. with brass cap
S.30° E.	52.40'	P.K. nail and O.C.R. tag S.W. face 18" Oak
S.58° W.	52.04'	P.K. nail and O.C.R. tag in N.W. face 20" Ash



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by _____ Date 2-16-95

Surveyor's Michigan License No. 17632