

MAR 11 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Oakland</u> (County)	Located in: Commerce Township	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>8E</u>	<u>J-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

\$ 7.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

6 NOV 98 10:01 A.M. RECEIPT# 28A  
PAID RECORDED - OAKLAND COUNTY

G. WILLIAM CAIDELL  
CLERK/REGISTER OF DEEDS  
ACT 345, P.A. 1990

APPROVED ON: 05-06-98 JS  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on August 12 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

J-5	1823	Wampler	G.L.O. Notes	Set Post
	1962	N/A	O.C.R.C. Section Corner Witnesses No. 57	Iron Pipe
	1986	Shanayda	Homestead Shores L. 9538 P. 899	N/A
	N/A	N/A	O.C. Tax Maps	N/A

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-5 Found a 1/2" rebar .5' West of the C/L of Newton Road (bit.) running North and South on the approximate line of a fence line running East and West. This corner checks recorded distance and angles shown in Homestead Shores L. 9538 P. 899. Measure angle J-6 from K-6 to J-5 as 91° 00' 17' (Homestead Shores = 90° 00' 18'). Accepted 1/2" rebar as the corner.

Measure West 2634.36' to I-5 (G.L.O. = 2659.14')  
Measure South 2624.44' to J-6 (Homestead Shores = 2624.54')  
Did not measure East to K-5 as it falls in Lower Straits Lake.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5 Replaced 1/2" rebar with a 5/8" x 24" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854." Also set a new monument box.

- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in N Side 14" Walnut N 75° W 21.68'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side P. Pole N 18° E 114.13'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side 14" Basswood N 15° W 53.25'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side P. Pole S 40° E 37.92'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date Aug 3, 1998  
EARTH TECH  
Surveyor's Michigan License No. 25854

