

**SURVEY & REMONUMENTATION**

Mar 10 95 040411

MAY - 1 1995

LIBER 15288 PG 497

\$ 7.00 MISC RECORDING CHG - IN HOUSE  
 \$ 2.00 REMON CHG - IN HOUSE  
 MAR 95 4:00 P.M. RECEIPT# 177B  
 RECORDED - OAKLAND COUNTY  
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970  
 Commerce Twp.

For corners in Oakland

(County)	Located in:	Corner Code #
1. Public Land Survey	T 2N R 8E	K-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**OK - T. SMITH**

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-05-94  
 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David Pawlaczyk, in a field survey on October 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Date	Description	G.L.O.	Name	Notes
1815	Post		A. Holmes	N/A
1984	1/2" Iron in monument box	L.C.R.C.	D. Finney	#15536 L8758 P611
1989	1/2" iron in monument box	L.C.R.C.	K. Schultz	#31610 L10966 P421

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A 1/2" iron rod in a monument box in asphalt pavement currently marks this corner. The following witness ties were used to recover and verify its position:

- 1 tie from L.C.R.C. L8758 P611
- 5 ties from L.C.R.C. L10966 P421

Field measurements were made between the following corners:

From	To	Distance	Method	Notes
K-10	K-9	2643.71	meas.	
		2640.00	rec. G.L.O.	Notes
		2643.88	rec. Plats	L91 P32 & L69 P31
K-10	K-11	2635.58	meas.	
		2640.00	rec. G.L.O.	Notes
		2635.55	rec. L.C.R.C.	L10966 P421
		2635.46	rec. Survey	Not recorded (D. Smith #33140)

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I placed a 2" diameter brass cap stamped "Oakland County Remonumentation PS #17632" on an existing 1/2" iron re-rod in the existing monument box in asphalt pavement.

- N.71° W. 83.71' P.K. nail and O.C.R. tag in N.E. face M.B.T. pole
- N.50° E. 37.08' P.K. nail and O.C.R. tag in N.W. face M.B.T. pole
- S.39° E. 100.12' P.K. nail and O.C.R. tag in N.E. face 48" Willow
- S.45° W. 81.56' P.K. nail and O.C.R. tag in S.E. face D.E. pole

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]

Date 2-16-95

Surveyor's Michigan License No. 17632

