

SURVEY & REMONUMENTATION

MAY - 1 1995

LIBER 15288 PG 499

MAR 10 95 040413

OK - T. SMITH

LAND CORNER RECORDATION CERTIFICATE \$ 7.00 MISC RECORDING CHG - IN HOUSE
 Filing Requirement of Act 74, Mich. P.A. 1970 \$ 2.00 REMON CHG - IN HOUSE
 Commerce Twp.

COMMISSION

For corners in Oakland

19 MAR 95 4:00 P.M. RECEIPT# 1778
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

(County) Located In: Corner Code #

1. Public Land Survey T 2N R 8E K-12
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Compliance with ACT 345, P.A. 1990
 APPROVED ON: 12-05-94
 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, David Pawlaczyk, in a field survey on November 30, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Date	Description	Surveyor	Notes
1815	Post	G.L.O. A. Holmes	N/A
1988	3/8" re-rod	L.C.R.C. R. Higgins	#21570 L11041 P604
1989	3/8" iron rod	L.C.R.C. K. Schultz	#31610 L10966 P424

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 5/8" iron rod in an existing monument box in asphalt pavement currently occupies this corner. The following witness ties were used to recover and verify its position:

- 3 ties from L.C.R.C. L10966 P424
- 1 tie from L.C.R.C. L11041 P604

Field measurements were made between the following corners:

From Corner	To Corner	Measurement	Method	Surveyor	Notes
K-12	K-11	2641.57	meas.		
		2640.00	rec.	G.L.O.	Notes
		2641.65	rec.	L.C.R.C.	L10966 P424
K-12	K-13	2641.36	meas.		
		2640.00	rec.	G.L.O.	Notes
		2641.63	rec.	L.C.R.C.	L10966 P424

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 2" diameter brass cap stamped "Oakland County Remonumentation PS #17632" on the existing 5/8" iron rod in the existing monument box in asphalt pavement.

- N.39° E. 34.61' P.K. nail and O.C.R. tag top of guard rail post
- East 42.97' 1/2" iron rod with O.C.R. tag
- S.17° E. 74.03' P.K. nail and O.C.R. tag top of guard rail post
- S.88° W. 59.45' Cut cross north rim sanitary manhole



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Date 2-16-95
 Surveyor's Michigan License No. 17632