

**SURVEY & REMONUMENTATION**

MAR 10 95 04 04 14

LIBER 15288 pc 500

OK - T. SMITH

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE 7.00 MISC RECORDING CHG - IN HOUSE

Filing Requirement of Act 74, Mich. P.A. 1970 2.00 REMON CHG - IN HOUSE

10 MAR 95 4:00 P.M. RECEIPT# 1779  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in **COMMISSION**  
Oakland

Commerce Twp.

(County) Located In: Corner Code #

1. Public Land Survey	T <u>2N</u> R <u>8E</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Compliance with ACT 345, P.A. 1990  
APPROVED ON: 12-05-94  
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

David Pawlaczyk November 29 94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1815 Post	G.L.O.	A. Holmes	N/A	Notes
1989 1/2" re-rod	L.C.R.C.	R. Higgins	#21570	L11041 P604
1989 Iron in mon. box	L.C.R.C.	K. Schultz	#31610	L10966 P424

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1/2" iron rod in a monument box in asphalt pavement currently occupies this corner. Two ties from L.C.R.C. L11041 P604 match existing monument box.

Field measurements were made between the following corners:

K-13 to L-13	2657.22	meas.		
	2640.00	rec.	G.L.O.	Notes
K-13 to J-13	2650.82	meas.		
	2640.00	rec.	G.L.O.	Notes
	2650.89	rec.	Condo.	O.C.C.P. 800
K-13 to K-12	2641.36	meas.		
	2640.00	rec.	G.L.O.	Notes
	2641.63	rec.	L.C.R.C.	L10966 P424

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 2" diameter brass cap stamped "Oakland County Remonumentation PS #17632" on the existing 1/2" iron rod in an existing monument box in asphalt pavement.

N.70° W.	98.39'	P.K. nail and O.C.R. tag in N.E. face D.E. pole
N.43° E.	46.04'	P.K. nail and O.C.R. tag in S.E. face D.E. pole
S.67° E.	82.61'	P.K. nail and O.C.R. tag in S. face MBT pole
S.21° W.	58.21'	P.K. nail and O.C.R. tag in W. face 12" Ash
West	222.00'	5/8" iron rod in monument box
North	60.00'	Found 1/2" iron rod #12583.



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by \_\_\_\_\_ Date 2-16-95

Surveyor's Michigan License No. 17632