

MAY 16 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland (County)

Located In: Commerce Twp. Corner Code #

- 1. Public Land Survey T 2N R 8E L-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. , Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-07-95 T.S.
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 2-13. A dot is present in cell J-9.

I, David Pawlaczyk, in a field survey on October 10, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with columns: Year, Description, G.L.O., Survey, Witness, Notes. Includes entries for 1823 Post, 1986 n/a, 1987 Set capped iron, 1989 Found 5/8" iron rod w/cap #24598.

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
27 DEC 95 9:55 A.M. RECEIPT# 54B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A capped 5/8" iron #24598 in a field currently occupies this corner. The following witness ties were used to verify and recover its position:

Table with columns: Ties match, Survey, Witnesses, License #. Includes 3 ties match survey Witnesses L12444 P296 and 5 ties match L.C.R.C. L10966 P418.

Field measurements were made between the following corners:

Table with columns: Corner pair, Distance, Measurement type. Includes K-9 to L-9 (2672.48 meas., 2668.05 Rec. G.L.O., 2672.07 unrecorded survey) and L-9 to M-9 (2672.04 L.C.R.C. L10966 P418, 2672.08 meas., 2668.05 Rec. G.L.O., 2672.72 Unrecorded survey).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the found capped iron with a 4" x 36" concrete monument with a 2" diameter brass cap stamped "Oakland County Remonumentation PS 17632"

- Due S. 30.46' Found P.K. & washer #24598 in W. face 18" Oak
S. 45° W. 26.76' Found P.K. & washer #24598 in S.E. face 16" Oak
S. 60° W. 10.87' Set O.C.R. witness tag in S.E. face 9" Cherry
S. 85° E. 50.49' Found P.K. washer #24598 in N. face triple 12" Cherry
S. 85° W. 25.92' Found P.K. washer #24598 in S.W. face 8" Elm



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]

Date 12-20-95

Surveyor's Michigan License No. 17632