

**SURVEY & REMONUMENTATION**

LIBER 15288 PG 502

MAR 10 95 040416

MAY - 1 1995

OK - T. SMITH

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISC RECORDING CHG - IN HOUSE  
\$ 2.00 REMON CHG - IN HOUSE  
10 MAR 95 4:00 P.M. RECEIPT# 1778  
PAID. RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

Oakland  
(County)

Located In: Commerce Twp Other Code #

- 1. Public Land Survey T 2N R 8E L-11  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 12-05-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, David Pawlaczyk in a field survey on December 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1815 Post	G.L.O.	A. Holmes	N/A	Notes
1979 1/2" Iron rod	L.C.R.C.	D. Finney	#15536	L7580 P811
1989 1/2" Iron rod	L.C.R.C.	K. Schultz	#31610	L10966 P423

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 3/4" iron pipe with MDOT cap in a wetland fringe currently occupies this corner. The following witness ties were used to recover and verify its present position:  
3 ties from L.C.R.C. L7580 P811  
5 ties from L.C.R.C. L10966 P423

Field measurements were made between the following corners:

L-11 to K-11	2660.93	meas.		
	2663.76	rec.	G.L.O.	Notes
L-11 to M-11	2654.27	meas.		
	2663.76	rec.	G.L.O.	Notes
	2654.69	rec.	L.C.R.C.	L10966 P423
	2656.67	rec.	Survey	L7659 P260

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the existing iron with MDOT cap with a concrete monument and a 2" diameter brass cap stamped "Oakland County Remonumentation P.S. 17632".

- N.76° W. 20.35' P.K. nail and O.C.R. tag in N. face 20" Willow
  - S.76° W. 36.00' P.K. nail and O.C.R. tag in N.W. face 14" Poplar
  - S.25° W. 35.43' P.K. nail and O.C.R. tag in N.W. face 32" Poplar
  - S.06° W. 16.65' Found "T" iron
- The iron falls just east of a Twin 6" Willow



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by

*[Signature]*

Date

2-16-95

Surveyor's Michigan License No.

17632