

SURVEY & REMONUMENTATION

MAY - 1 1995

COMMISSION

LIBER **15288** PG **494**

MAR 10 95 408

\$ 7.00 NISC RECORDING CHG - IN HOUSE
 \$ 2.00 REMON CHG - IN HOUSE
 MAR 95 3:59 P.M. RECEIPT# 1778
 RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 Commerce Twp.

For corners in Oakland

(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 2N R 8E M-8
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

OK - T. SMITH

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 12-13-94
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, David Pawlaczyk, in a field survey on October 25, 1994
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law, established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Date	Monument	Surveyor	Notes
1815	Post	G.L.O. A. Holmes	N/A
1976	"T" Iron	Survey L. Howison	#1840
1976	"T" Iron	L.C.R.C. L. Howison	#1840
1978	"T" Iron	Survey D. Finney	#15536
1978	"T" Iron	L.C.R.C. D. Finney	#15536
1992	Iron in asphalt	Survey M. Zuhlke	#17641

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A "T" iron 0.5' below top of asphalt pavement currently occupies this corner. No witness ties were found from existing L.C.R.C.

Field measurements were made between the following corners:

From	To	Measurement	Method	Notes
M-8	M-7	2664.01	meas.	
		2640.00	rec.	G.L.O.
		2664.24	rec.	Survey
M-8	M-9	2650.65	meas.	
		2640.00	rec.	G.L.O.

7/10
2/12

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the found "T" iron in asphalt pavement with a 5/8" x 24" iron rod with a 2" diameter cap stamped "Oakland County Remonumentation PS #17632" with a new monument box.

S.45° W.	113.27'	P.K. nail and O.C.R. tag in S.E. face 20" Pine
N.86° W.	68.28'	Found P.K. nail and tag #24598 in N. face D.E. pole
S.35° E.	147.63'	P.K. nail and O.C.R. tag in S.W. face 12" Ash
N.58° W.	137.27'	P.K. nail and O.C.R. tag in concrete footing at southerly bldg. corner.
Due south	370.83'	Found 1/2" iron in asphalt pavement



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]

Date 2-16-95

Surveyor's Michigan License No. 17632