

SURVEY &
REMONUMENTATION

MAY 24 2000

LIBER 21119 635

51704

SECTION

LAND CORNER RECORDATION CERTIFICATE LIBER 21119 PAGE 635
Filing Requirement of Act 74, Mich. P.A. 1970

\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/18/2000 02:36:27 P.M. RECEIPT# 14203
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

Oakland (county)	Located In:	Corner Code #
	Bloomfield Township	
1. Public Land Survey	T2N R10E	K-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

12-7-99 JN

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on July 14, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	
2													
3													
4													
5													
6	13	17	19	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1817 G.L.O. survey.
There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 5/8" rerod in monumentation box on centerline South Blvd. 149.41' east of K-13 Pontiac Township and on the township line. Validated this location with monumentation found on north and east lines of SHAKER HEIGHTS SUBDIVISION and south line of HUNT CLUB SUBDIVISION.

Recovered witnesses:

- * S 09°W 58.92' PK nail with survey marker tag east side power pole
- S 09°W 59.00' Doubleheaded nail with bottle cap east side power pole
- S 09°W 58.28' Doubleheaded nail with OCRC tag north side power pole

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County Remonumentation Brass Cap #24598 on existing 5/8" rerod in monument box.

Set witnesses:

- * S 09°W 58.92' PK nail with OCRT #24598 east side power pole.
- N 41°W 89.84' PK nail with OCRT #24598 northeast side 12" Maple.
- N 75°W 131.03' chiseled cross on center top nut on fire hydrant.
- S 71°W 180.65' PK nail with OCRT #24598 southeast side power pole.

* Reused recovered witness



Signed by Joseph C. Kapelczak

Date 12/22/99

Surveyor's Michigan License No. 24598