

SURVEY &
REMONUMENTATION

MAR 04 1998

LIBER 17038 PG 729

SECTION

FIELD MEASUREMENTS BETWEEN

I-7 to H-7

GLO = 40.555 chains 2676.63 Ft.
MCS 2684.81 Ft. No date stated
"SUPERVISOR'S PLAT NO. 14" + 20-15-451-035 & 036, 2684.80 Ft.
"NORTHGATE SUBDIVISION" 2684.12 Ft.
GPS-MEA 2685.03 Ft.

I-7 to I-8

GLO = 40 chains or 2640.00 Ft.
MCS 2807.04 Ft. No date stated
Total of parcel from sidwell on the East side
of Rochester Road 2807.81 Ft.
"NORTHGATE SUBDIVISION" + "HIDDEN RIDGE SUBDIVISION" + "CLOVERDALE FARMS"
+ "SUPERVISOR'S PLAT NO. 6" 2807.34 Ft.
GPS-MEA = 2807.30 Ft.

I-7 to J-7

GLO = 39.83 chains or 2628.78 Ft.
MCS 2652.97 Ft. No date stated
"SUPERVISOR'S PLAT OF SQUARE ACRES SUBDIVISION", 2653.99 Ft.
"RAINTREE VILLAGE SUBDIVISION NO.3" + 20-23-100-002 thru
007 & 044-045, 2652.11 Ft.
GPS-MEA 2653.59 Ft.