

MAR 04 1998

LIBER 17156 PG 256

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland

(County)

Located In: Troy Twp. Corner Code #

1. Public Land Survey	T	2N	R	11E	J-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

\$ 9.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 24 APR 97 8:47 A.M. RECEIPT# 55A
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
 Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 3-25-97 JS
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on 1/7, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 8" Lynn N84°W 19 Links; 8" Birch N81°E 20 Links
 1.) 1977-McMahon, PS #4018; LCRC L.7070, Pg.136 - Fnd Railroad Spike
 2.) 1989-Donnelly, PS #21563; L.11062, Pg.215 - Fnd "T" Iron w/RLS #21566
 3.) 1993-Avey, PS #15396; Survey L.13281, Pg.751 - Fnd 1/2" Bar w/cap #33140
 4.) 1945-Nampa, RLS; Unrecorded Survey - Object found not stated, no witnesses

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd capped 1/2" Iron Rod #33140 5" below the surface in the center median of Big Beaver Road extending to the East & West, which has a concrete surface. A tree row extending to the North.

Witnesses from LCRC #2, Survey #3 and unrecorded Survey #4 were used to recover and verify the location of the found capped 1/2" Iron Rod #33140.

I accepted the found capped 1/2" Iron Rod #33140 as the best evidence of the original corner position.

Field measurements between see back side of LCRC

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 J-9 I replaced the found 1/2" Iron Rod with a 4" diameter Concrete Monument with a 1/2" Iron Rod 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
 Due North 109.33' Set PK & Remon Washer North face 50" clump Oak
 Due West 5.33' Center of Steel Light Post
 S03°W 98.98' Set PK & Remon Washer West face Power Pole
 S38°E 204.72' Set PK & Remon Washer NE face Power Pole
 North 101.89 Ft. Fnd 1/2" Iron Rod

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
 Surveyor's Michigan License No. 17623

Date 3/20/97



7A
SURVEY &
REMONUMENTATION

MAR 04 1998

SECTION

LIBER 17156PG257

FIELD MEASUREMENTS BETWEEN

J-9 to I-9

GLO = 39.58 chains or 2612.28 Ft.
Herbert G. Avey, PS #15396 (1/25/93) = 2610.20 Ft.
George L. Nampa, Ps (9/13/45) = 2609.80 Ft.
"SUPERVISOR'S PLAT NO. 11" + Parcels = 2607.50 Ft.
GPS-MEA = 2609.84 Ft.

J-9 to K-9

GLO = 39.58 chains or 2612.28 Ft.
"LASIER GARDENS SUBDIVISION" + Parcels = 2646.05 Ft.
GPS-MEA = 2642.70 Ft.