

**SURVEY & REMONUMENTATION**

MAR 04 1998

LIBER 17325 PG 333

\$ 9.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
JUN 97 3:38 P.M. RECEIPT# 1794  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland  
(County)

Located In: Troy Twp. Corner Code #

1. Public Land Survey	T	<u>2N</u>	R	<u>11E</u>	<u>K-13</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Compliance with ACT 345, P.A. 1990  
APPROVED ON: 6-5-97 JS  
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on 5/14, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
1817-GLO Wampler, D.S.; Set Post 8" Elm S60°W 27 Links; 9" Sugar N11 1/2°W 10 Links  
1.) 1977-McMahon, PS #4018; LCRC L.7070, Pg.134 - Fnd Handhole  
2.) 1993-Higgins, PS #21570; LCRC L.13474, Pg.151 - Fnd 1" Bar in a Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1" Iron Rod in a Monument Box in the intersection of John R. Road extending to the North & South, which has a concrete surface, Big Beaver Road extending to the East & West, which has a concrete/bituminous surface.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 1" Iron Rod in a Monument Box.

I accepted the found 1" Iron Rod in a Monument Box as the best evidence of the original corner position.

Field measurements between see back side of LCRC

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
K-13 I replaced the found 1" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in an existing Monument Box  
S49°E 89.91' Set PK & Remon Washer NE face Power Pole  
S46°W 90.58' Set PK & Remon Washer NW face Power Pole  
N39°E 161.42' Set PK & Remon Washer NW face Power Pole  
N40°W 141.25' SE corner of the East leg of sign for the Oakland Mall

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

900 FILE  
200 ✓



Signed by [Signature]  
Surveyor's Michigan License No. 17623

Date 6-6-97

SURVEY &  
REMONUMENTATION

LIBER 173250334

MAR 04 1998

SECTION

FIELD MEASUREMENTS BETWEEN

K-13 to J-13

GLO = 40 chains or 2640.00 Ft.

Sidwell = 2657.27 Ft.

GPS-MEA = 2657.34 Ft.

K-13 to K-12

GLO = 40 chains or 2640.00 Ft.

MCS, date not stated = 2640.66 Ft.

GPS-MEA = 2640.00 Ft.

K-13 to L-13

GLO = 40 chains or 2640.00 Ft.

MCS = 2668.96 Ft.

"ROBBINS EXECUTIVE PARK EAST NO. 5" + "ROBBINS EXECUTIVE PARK EAST" + Parcels = 2669.42 Ft.

GPS-MEA = 2669.40 F.