

SURVEY & REMONUMENTATION

LIBER 17277 PG 679

MAR 04 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970


For corners in SECTION

Table with columns: Located in: City of Troy, Corner Code #, and rows for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990. APPROVED ON: 3-26-97 RS. OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE. \$ 9.00 MISCELLANEOUS RECORDING \$ 2.00 REMONUMENTATION 9 JUN 97 12:18 P.M. RECEIPT# 94A PAID RECORDED - OAKLAND COUNTY

4. Lot No. , Recorded Plat
5. Private Claims

I, Randy Kolehouse, in a field survey on March 5 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:



NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Table with columns: Description of original monument and accessories and/or subsequent restoration, M-3, 1816, 1949, 1972, Wampler, McGarth, Nowak, G.L.O. Notes, Survey, L.C.R.C. L. 5900 P. 273, Set Post, N/A, 1/2" Rerod

(Continued on Back)

Records indicate this corner is common with A-3, T2N, R12E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: M-3 Found a Macomb County Monument in a monument box at the C/L intersection of Dequindre Road (bit.) running North and South, 19 Mile Road (bit.) running East, and Square Lake Road (bit.) running West per L.C.R.C.'s L. 5900 P. 273, L.C.R.C. L. 11062 P. 211, L.C.R.C. L. 10956 P. 331 and an unrecorded L.C.R.C. by Wilkerson. Checks L.C.R.C.'s L. 02380 P. 494, L. 02886 P. 441 and L. 06779 P. 621 Macomb County Records. Also checks closely distances as shown in recorded plats and the Oakland County tax records.

- L.C.R.C. L. 5900 P. 273 (1972) N 70° W 81.98' PK Nail in P.P. (m. 82.05')
L.C.R.C. L. 11062 P. 211 (1986) Az 160° 122.74' PK Nail w/RJD Flasher W Face U.P. (m. 122.61) Az 225° 60.89' C/L Fire Hydrant (m. 60.80') Az 320° 97.97' NE Ccorner Bldg.
L.C.R.C. L. 10956 P. 331 N 60° W 82.38' N/W NE Face P.P. (m. 82.27')
Unrecorded L.C.R.C. (1993) N 60° W 82.40' Nail/Tag NE Face U.P. (m. 82.27')

Measure North 2649.06' to M-2 (G.L.O. = 2640.0') (Warwick Woods Sub. = 2649.75')
Measure South 2653.62' to M-4 (G.L.O. = 2640.0') (O.C. Tax Maps = 2653.40')
Measure West 2592.05' to L-3 (G.L.O. = 2635.4') (O.C. Section Info. = 2592 ±) (Shariwood Sub. 2592.2')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: M-3 Macomb County Monument in an Existing Monument Box PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side Util. Pole N 50° E 58.80' PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side Util. Pole N 60° W 82.27' PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side Util. Pole S 45° W 71.03' PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side Util. Pole S 35° E 67.92'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy Kolehouse Date 5/20/97

Surveyor's Michigan License No. 25854



## A. Description of original monument and accessories and/or subsequent restoration:

M-3	1973	Ross	L.C.R.C. L. 7533 P. 837	1/2" Iron
	1973	Patterson	L.C.R.C. L. 2380 P. 494 (Macomb Co.)	Iron in Hand Hole
	1977	Walker	Survey	N/A
	1977	Walker	Survey	N/A
	1977	Walker	Survey	N/A
	1977	Walker	Survey	N/A
	1977	Walker	Survey	N/A
	1977	Patterson	L.C.R.C. L. 02886 P. 441	Iron in Mon. Box
	1983	Donnelly	Survey	N/A
	1986	Donnelly	L.C.R.C. L. 11062 P. 211	1/2" Pipe
	1988	Kennedy	L.C.R.C. L. 10956 P. 331	1/2" Iron Rod
	1988	Kennedy	Survey	N/A
	1993	Patterson	Warwick Woods Sub. L. 223 P. 17	N/A
	1993	Kennedy	Shariwoods Sub. L. 223, P. 26	N/A
	1993	Wilkerson	L.C.R.C.	3/4" Iron
	1995	Kolehouse	L.C.R.C. L. 06779 P. 621 (Macomb Co.)	Macomb Co. Mon. in Mon. Box
	N/A	N/A	O.C. Section Information	N/A
	N/A	N/A	O.C. Tax Maps	N/A