

X
 8
 8
 8
 8
 7.5

Y
 2
 1
 0
 1
 1.5

Iron pipe in W side rd. S 33° 45' E 29.50 6" pipe
 (P. Co. Rd. Comm) S 59° 15' W, 35.2 spike in N side Twin oak (1959) Reported to Co Rd Comm
 S 25° 35' W 29.7 " " good Hickory
 3/4" x 30" IR N side rd. S 19° E 48" R. oak horiz spike in W side; S 20° S 21
 2 1/2" N 7/8" Rd. (1957) S 77° W 48" Whitewood, " " N. 1/2 x 1/2
 Brass cap, stamped riveted to iron pipe
 Located in old fence lines. Double corner on Twp Line
 Sec. 34, E 1/4 cor, 3/4 x 30" iron pipe 21' N of 4 of Reid Road; S 18° W, 48.66'
 14" Oak horiz spike; S 83° 45' W 43.79 48" Whitewood horiz spike (1957)
 Reported to Co Rd Comm.
 SW cor NE 1/4 of NE 1/4 of sec 34 1/2" iron pipe level with ground S 0° W 8.0" fence post
 N 95° W 38.53' 7" open horiz spike; S 12° W 7.53' 2" wild cherry (1952) horiz spike
 Reported to Co Rd Comm.