

Grant J. Ward
LICENSED LAND SURVEYOR

CERTIFICATE OF SURVEY

THIS CERTIFICATE IS VALUABLE, FILE IT WITH THE DEED OR ABSTRACT FOR THIS PROPERTY.

WITNESSES TO GOVERNMENT CORNERS

I-10 West 1/4 Corner Sec. 26, T. 3 N., R. 7 E., Found Large Spike

Previously recorded in Liber 7844, Page 93 (*Only one accessory remains)

- * S 33° E N. W/S 50" Oak 35.35' (30" Oak)
- S 40° E 35.07' Spike & Washer #22445 in Northwest side of 30" Oak
- S 05° E 126.46' Spike & Washer #22445 in West side of 36" Oak
- S 15° W 77.71' Spike & Washer #22445 in East side of 24" Oak
- S 65° W 67.99' Spike & Washer #22445 in East side of 15" Oak
- West 33.39' C/L of top of 4" diameter Steel Fence Post

J-9 North 1/4 Corner Sec. 26, T. 3 N., R. 7 E., Found Iron Rod

- N 10° E 23.53' Spike in West side of 30" Oak
- S 50° E 51.49' Spike & Washer #22445 in Southwest side of 36" Oak
- S 80° W 75.84' Spike & Washer #22445 in North side of 24" Oak
- S 50° W 43.46' Spike & Washer #22445 in Northwest side of twin 8" Tree

J-10 Center of Section 26, T. 3 N., R. 7 E., Set Iron Rod and Cap #22445

- North 24.72' Spike & Washer #22445 in West side of twin 16" Oak
- S 75° E 2.55' Spike & Washer #22445 in South side of 16" Oak
- S 30° W 16.91' Spike & Washer #22445 in Northwest side of twin 18" Oak
- S 80° W 37.05' Spike & Washer #22445 in North side of twin 14" Oak

J-11 South 1/4 Cor. Sec. 26, T. 3 N., R. 7 E., Set Iron Rod and Cap #22445

- North 44.02' Spike & Washer #22445 in West side of twin 18" Oak
- N 80° E 3.10' Spike & Washer #22445 in South side of 28" Oak
- South 74.82' Spike & Washer #22445 in West side of twin 20" Oak
- N 60° W 38.27' Spike & Washer #22445 in North side of 18" Wild Cherry

K-9 Northeast Corner Sec. 26, T. 3 N., R. 7 E., Found 1" Iron Pipe W/Cap

Previously recorded in Liber 8243, Page 120 (Accessories in poor condition)

- N 75° W 3.78' Found Iron Rod as recorded in Liber 6770, Page 863
- S 80° W 48.20' Found Nail & D.N.R. Washer in N. side of Trip. 8" Box Elder
- N 20° W 69.76' Spike & Washer #22445 in West side of twin 28" Oak
- N 30° W 50.13' Fd. Nail, set S & W #22445 in East side of 22" Oak

K-10 East 1/4 Corner Sec. 26, T. 3 N., R. 7 E., Found Concrete Monument

As recorded in Liber 8243, Page 118 (Accessories in good condition)

- N 57° E 22.93' 5" Soft maple twin
- S 85° E 44.31' 6" Maple
- S 04° W 20.31' 15" Oak
- N 77° W 25.73' 15" W. Oak

K-11 Southeast Corner Sec. 26, T. 3 N., R. 7 E., Found Concrete Monument

As recorded in Liber 8243, Page 118 (Accessories in good condition)

- N 16° E 16.60' 20" B. Oak
- East 13.42' 20" R. Oak
- S 11° W 33.18' 30" W. Oak
- S 75° W 35.23' 24" B. Oak

LEGEND

- C - CALCULATED
- M - MEASURED
- R - RECORDED
- S - SET
- F.I.P. - FOUND IRON PIPE
- F.I.R. - FOUND IRON ROD
- F.M. - FOUND MONUMENT
- F.P.P. - FOUND PINCH PIPE
- S.I.R. - SET IRON ROD
- S.I.R. & C. - SET IRON ROD & CAP

DATA TAPE 14
DATA FILE F1203
JOB NO. 84-1203
SHEET NO. 5 of 5

SURVEYOR'S CERTIFICATE

I, Grant J. Ward, a Licensed Land Surveyor in the State of Michigan, certify that I have surveyed and mapped the land above described on JANUARY 10, 1985, and that the Ratio of Closure of the unadjusted field observations of such Survey was 1:45,000 and that all of the requirements of Public Act 132 of 1970 have been complied with.

Licensed Land Surveyor No. 22445

Client: DR. CLARK LEMLEY
1020 BEAUMONT
HIGHLAND MICHIGAN 48031



SEAL