

# LAND CORNER REGISTRATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

**OAKLAND**

FOR CORNER OF:	LOCATED BY:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY 25	T. 3 N., R. 7 E.	L-9, R-9
2. PROPERTY CONTROL- ING IN SECTION	N. S., R.	E. W.
3. MISCELLANEOUS PROPERTY IN SECTION	N. S., R.	E. W.
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

NUMBER OF CORNERS AND  
EVIDENCE FOUND

I, Donald L. Bissell, do hereby certify that under provisions of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 19, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules then in effect as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on June 19, 1982, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in locating or re-establishing corner:

<p>L-9 Found: 1/2" Iron Rod with Mich. Dept. of Trans. &amp; Treasurers S. 49°E. 31.45' 18" Oak S. 61°W. 51.93' 12" Oak N. 49°W. 65.85' 33" Oak Set: 1" Iron Pipe with Plastic Cap.</p>	<p>R-9 Found: 1/2" Iron Rod with metal Locator Set: 1" Iron Pipe with Plastic Cap #18655.</p>
---	---

C. Description of monument for corner or accessories established to perpetuate location of the corner:

<p>L-9 1" Iron Pipe with Plastic Cap S. 63°E. 51.76' 12" W. Oak R. 65°E. 48.66' 14" W. Oak S. 47°E. 31.15' 30" W. Oak N. 47°W. 65.92' 33" W. Oak</p>	<p>R-9 1" Iron Pipe with Plastic Cap S. 74°E. 55.09' 24" Poplar S. 50°E. 22.75' 10" Box Elder S. 79°W. 48.25' 6" Triple Box Elder N. 32°W. 50.13' 24" Oak</p>
--	---

SIGNED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ COUNTY \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

APPROVED AND SIGNED BY: Donald L. Bissell DATE: 6-17-82  
MICHIGAN REGISTERED LAND SURVEYOR COUNTY \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655