

**LAND CORNER RECORDATION CERTIFICATE**  
**FILED REQUIREMENT OF ACT 76, MICHIGAN LAWS 1970**

**OAKLAND**

FOR CORNER OR PT.	LOCATED IN:	COTTER CODE NUMBER
1. PUBLIC LAND SURVEY	25 T 3 R 11 sec 7 E. W.	K-11, K-10
2. PROPERTY CONTROL IN SECTION	N. S., R.	E. W.
3. MISC. ELABOROUS PROPERTY IN SECTION	N. S., R.	E. W.
4. LOT NO.	, RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTRATION FORMS APPROVED  
MICHIGAN STATE BOARD OF SURVEYORS

I, Donald L. Blaneff, do hereby certify that under requirements of P.A. 74, Michigan P.L. of 1970, the corner points mentioned in Lines 1 and 2 above were, in a field survey on June 1, 1962, established, re-established, remonumented, resurveyed, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current model of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in Lines 3, 4 and 5 above were, in a field survey on June 1, 1962, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of Law:

A. Description of original monument and access, if any, and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K-11 Found: Old Fence Corner.  
Checked with ties to the  
N. and E. Gov't. Corners.  
Set: 4" x 36" Concrete  
Monument with Alabama  
cap.

K-10 Set 4" x 36" concrete monument  
mid-way and on line between N & S  
sec. corners, also checks sweep  
tie to the North.

C. Description of monument for corner and accessories established to positively locate the position of the corner:

K-11 4" x 36" Concrete monument  
R. 16°E. 16.60' 20" B. Oak  
East 13.42' 20" R. Oak  
S. 11°W. 33.18' 30" W. Oak  
S. 75°W. 35.23' 29" B. Oak

K-10 4" x 36" Concrete monument  
K. 57°E. 22.93' 5" Soft maple  
twin  
S. 85°E. 44.31' 6" Maple  
S. 04°W. 20.31' 15" Oak  
E. 77°W. 25.73' 15" W. Oak

SIGNED BY

DATE

SURVEYOR'S MICHIGAN REGISTRATION NO.

GRADE

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

DATE

APPROVED AND SIGNED BY, *Donald L. Blaneff, P.L.S.*  
Michigan Registered Land Surveyor

DATE, 07/27/62

(initials)

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS JAN. 2, 1971  
REVISED MAY 12, 1972

MAY PLACE SKETCH ON BACK OR IN ENCL. DRAFT