

# LAND CORNER RECORDATION CERTIFICATE

FIELD REQUIREMENT OF 1957 PA. 74, MICH. PA. 19570

**OAKLAND**

FOR CORNER OF:	25	T. 3	N. 7	E. 1/2	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY					1-11
2. PROPERTY CONTROLING IN SECTION					16
3. MISCELLANEOUS PROPERTY IN SECTION					
4. LOT NO. _____, RECORDED PLAT _____					
5. PRIVATE CLAIM _____					

LEGISLATIVE DEPARTMENT  
LAND SURVEY

I, Donald L. Johnson, do hereby certify that the requirements of P.A. 74, Michigan P.A. of 1957, the corner points mentioned in lines 1 and 2 above were, in a field survey on \_\_\_\_\_, June \_\_\_\_\_, 1962, established, re-established, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring, or re-establishing corner:  
 1-11 Found: 1/2" Iron Rod with Plastic cap, 8" below Gravel surface. Found with metal locator. #16 Set 4" x 35" Concrete Monument Mid-way and on line between S. E. and S 1/4 corners of Sec.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 1-11 1/2" Iron Rod #16 4" x 35" Concrete Monument  
 N. 55° E. 32.95' 6" Cherry S. 41° E. 20.83' 4" Elm  
 S. 55° E. 42.09' 6" Oak S. 76° W. 21.33' 4" Elm  
 S. 54° W. 34.06' 6" Fruit tree N. 22° E. 20.95' 17" Oak  
 Monument is the N. bank of and E-W ditch.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY *Donald L. Johnson* DATE *8-17-62*  
MICHIGAN BOARD OF LAND SURVEYORS (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

MAY BE CUT, SLIT ON BACK OR ATTACHED SHEET