

WITNESSES - SECTION 27, T3N, R7E

W 1/4 Corner *G 1-5*  
 Found 1/2" iron set by Boss at intersection  
 of N-S fence and west fence.  
 East, 25.34', 15" Pine, Nail  
 North, 12.38', 8" Cherry, Nail  
 West, 97.93', Quad. Mulberry, Nail

N 1/4 Corner *H 1-1*  
 Found re-rod from witnesses by John Albright.  
 East, 10', End of blacktop  
 South, 1', South edge of blacktop  
 S 70° W, 60.96', Power Pole, Tag #17623  
 N 50° W, 55.25', Large Willow Clump, Tag #17623  
 N 40° W, 43.48', 50" Willow, Tag #17623  
 N 5° W, 38.72', 60" Willow, Spike (Albright)

C 1/4 Corner *H 1-1*  
 Set 1"x 48" pipe with DNR cap in 4" tile with  
 concrete at the intersection of the 1/4 lines.  
 S 15° W, 25.38', 15" Cherry, Spike and Tag  
 West, 14.58', 6" Cherry, Spike and Tag  
 North, 15.14', 5" Cherry, Spike and Tag  
 S 35° E, 31.48', 9" Walnut, Spike and Tag

S 1/4 Corner *H 1-1*  
 Found wood stake; replaced with 4"x 36" concrete  
 monument with DNR cap; on north side of house  
 #1831.  
 S 70° E, 12.00', 16" Tamarack, Spike and Tag  
 S 40° E, 7.25', NE corner block chimney  
 S 22° W, 5.38', NW corner block chimney  
 S 75° W, 13.07', NW corner smaller block  
 chimney

E 1/4 Corner *I-10*  
 Found 3/4" pipe from Boss witnesses.  
 S 33° E, 35.35', 50" Oak, Nail  
 S 20° W, 77.69', Tw. Oak, Nail  
 N 28° W, 30.00', 40" Oak, Nail

SE Corner *T-11*  
 Found 1" iron pipe from witnesses  
 furnished by Oakland Co. Road Comm.  
 In West Edge of Road  
 S 55° W, 25.65', 15" W. Oak, Spike  
 and Tag  
 West, 34.75', Twin 14 + 20" W. Oak  
 Spike and Tag  
 N 47° W, 46.96', 15" R. Pine, Spike  
 and Tag  
 S 69° E, 51.54', 15" Box Elder,  
 Spike and Tag

N 1/8 Corner, SE 1/4 *S 1-9*  
 Set 1"x 10' pipe with DNR cap inside  
 4" tile filled with concrete.  
 N 65° W, 21.15', 10" Tamarack, Spike  
 N 25° E, 2.83', 6" Tamarack, Spike  
 S 65° E, 8.70', 6" Tamarack, Spike  
 S 20° E, 9.47', 6" Tamarack, Spike  
 South, 26', North edge of lake.

E 1/8 Corner, SE 1/4 *G 1-11*  
 Set 3/4" pipe halfway on line between  
 SE corner and E 1/4 corner.  
 S 75° E, 30.12', 20" Hickory, Spike  
 and Tag  
 S 32° E, 48.53', 20" Hickory, Spike  
 and Tag  
 S 35° W, 36.76', 16" Hickory, Spike  
 and Tag  
 N 88° W, 52.68', Power Pole, Spike  
 and Tag  
 East, 4' E Road

C 1/8 Corner, SE 1/4 *S 1-10*  
 Set 4"x 36" concrete monument with  
 DNR cap.  
 S 77° W, 40.70', Triple 6, 8, and 10"  
 Willow, Spike and Tag  
 N 7° E, 25.55', 15" Tamarack, Spike  
 and Tag  
 N 55° E, 63.63', 18" W. Oak, Spike  
 and Tag

MICH. DEPT. OF NATURAL RESOURCES	
REGION III Parks	
HIGHLAND R.A., Sec. 27, T3N, R7E	
LOCATION Oakland County	
SURVEYED BY D.L. Bissell	DATE 6-80
DRAWN BY D.J. Reed	DATE 6-80
SHEET 2 OF 2	# 03-6175