

**SURVEY & REMONUMENTATION**

LIBER 20560 188

MAY 24 2000

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

345415

For corners in

**SECTION**

LIBER 20560 PAGE 408  
\$3.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
09/20/1999 08:42:41 A.M. RECEIPT# 79775  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Oakland  
(County)

Located In: Highland Township Corner Code #

- |                                    |   |   |     |
|------------------------------------|---|---|-----|
| 1. Public Land Survey              | T | R | A-5 |
|                                    | T | R |     |
|                                    | T | R |     |
|                                    | T | R |     |
| 2. Property Controlling in Section | S | T | R   |
|                                    | S | T | R   |
| 3. Miscellaneous Property in Sec.  | S | T | R   |
|                                    | S | T | R   |

Compliance with ACT 345, P.A. 1990

APPROVED ON: 8-4-99 JH  
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
1817-GLO Holmes, D.S.; Set Post 9" White Oak S62°E 1.10 chains; 7" White Oak N78 1/2°E 14 Links  
1.) 1995-Smith, PS #35999; LCRC for (M-5 Hartland Twp.) LSC #505m - Fnd a 1/2" Iron Pipe  
2.) 1991-Brady, PS #32333; Unrecorded Survey - Fnd a 3/4" Pipe  
3.) 1971-Albright, PS #10057; Unrecorded Survey - Object found not stated, no witnesses  
4.) 1962-Oakland County Road Commission Unrecorded Witnesses - Fnd a 3/4" Pipe

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1-1/4" Steel Pipe with a 2" diameter brass cap stamped Livingston County Monument Corner PS #35999 located in the existing centerline of Tipsico Lake Road which extends to the North & South, which has a gravel surface, also located in the centerline of Middle Road extending to the East & West, which has a gravel surface. This corner is being accepted and used as a common corner with Sections 12 & 13, T3N, R6E, Hartland Township (M-5).

Witnesses from LCRC #1 & Unrecorded Survey #2 were used to recover and verify the location of the found 1-1/4" Steel Pipe with a 2" diameter brass cap stamped Livingston County Monument Corner PS #35999

I accepted the found 1-1/4" Steel Pipe with a 2" diameter brass cap stamped Livingston County Monument Corner PS #35999 as the best evidence of the original corner position.

**FIELD MEASUREMENTS BETWEEN**

**A-5 to A-4**  
No GLO.  
No sidwell or plat distances  
2651.16 FL (GPS-MEA)

**A-5 to B-9**  
GLO = 30 chains or 1980.00 Ft.  
Unrecorded Survey by John D. Albright, PS #10057 dated 5-23-97  
Unrecorded Survey by Matthew A. Brady, PS #32333 dated 5-23-97  
1988.39 FL (GPS-MEA)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
A-5 I accepted the 1-1/4" Steel Pipe with 2" diameter brass cap stamped Livingston County Monument Corner PS #35999  
N74°E 115.02' Set Mag Nail & Remon Washer South face 30" Oak  
N43°W 42.98' Set Mag Nail & Remon Washer NE face Guide Pole  
S71°E 93.87' Set Mag Nail & Remon Washer North face 32" Oak  
S47°W 42.78' Set Mag Nail & Remon Washer NW face 44" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]  
Surveyor's Michigan License No. 17623

Date 8-5-99

