

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 21077 PAGE 425
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/08/2000 09:02:23 A.M. RECEIPT# 1018
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF D

For corners in

Oakland
(County)

Located In: Highland Township
Corner Code #

- 1. Public Land Survey T3N R7E A-9
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

SURVEY &
REMONUMENTATION
FEB 1 2000

Compliance with
ACT 68, P.A. 1999

APPROVED ON: 1-12-2000 JH
OAKLAND COUNTY REMONUMENTATION
SURVEY & REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____ SECTION _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on October 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; Set Post 9" White Oak S24°E 45 Links; 8" Black Oak S58°W 22 Links
1.) 1976-Hooth, PS #7966; LCRC L.6770, pgs.839 & 840 - Fnd a PK Nail
2.) 1994-Smith, PS #35999; LCRC for (M-9 Highland Twp.) L.S.C. #272m - Fnd MSHD stamped Iron in a Monument Box
3.) 1962-Oakland County Road Commission unrecorded witnesses - Fnd a Spike
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 2" diameter brass cap stamped Livingston County Monument Corner in a Monument Box located in the existing centerline of the East bound lane of M-59 Highway extending to the East & West, which has a bituminous surface, also in the existing centerline of Tipsico Lake Road extending to the North, which has a bituminous surface and to the South, which has a gravel surface.

Witnesses from LCRC #2 & local monumentation were used to recover and verify the location of the found 2" diameter brass cap stamped Livingston County Monument Corner in a Monument Box.

I accepted the found 2" diameter brass cap stamped Livingston County Monument Corner in a Monument Box as the best evidence of the original corner position.

Field measurements see back side

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-9 I accepted the found 2" diameter brass cap stamped Livingston County Monument Corner in a existing Monument Box
N45°W 40.55' Fnd 1" Iron Pipe with brass cap stamped Livingston County Monument Witness #35999
N60°E 50.70' Fnd 1" Iron Pipe with brass cap stamped Livingston County Monument Witness #35999
S45°E 58.30' Fnd 1" Iron Pipe with brass cap stamped Livingston County Monument Witness #35999
S45°W 64.90' Fnd 1" Iron Pipe with brass cap stamped Livingston County Monument Witness #35999

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 12-18-99



1998-01-01

1. 21. 1011 01
1998-01-01

2. 01. 1011 01

FIELD MEASUREMENTS BETWEEN

A-9 to A-9

No GLO

"VAN SCHOICKS SUBDIVISION" + "TIPSICO ESTATES NO. 1" (Sec 19) = 2640.98 Ft.

M.DOT Right of Way Map = 2640.69 Ft.

2640.42 Ft. (GPS-MEA)

A-9 to A-10

No GLO

Sidwell W 1/2 of NW 1/4 Sec 30 (11-30A) Sec 19 = 2647.68 Ft.

M.DOT Right of Way Map = 2632.29 Ft. (M-10, T3N, R6E)

2647.65 Ft. (GPS-MEA)

A-9 to B-9

GLO = 29.40 chains or 1940.40 Ft.

"VAN SCHOICKS SUBDIVISION" (Sec 19) = 1960.32 Ft.

M.DOT Right of Way Map = 1959.85 Ft.

1959.26 Ft. (GPS-MEA)

SURVEY &
RECORDS DIVISION

MAR 21 2000

SECTION