

LIBER 20329 PG 643

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

273077

LIBER 20329 PAGE 643
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
07/29/1999 11:46:12 A.M. RECEIPT# 5891
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

Oakland
(County)

Located In: Highland Township
Corner Code #

1. Public Land Survey

T3N R7E B-3

2. Property Controlling in Section

S T R SURVEY & REMONUMENTATION

3. Miscellaneous Property in Sec.

S T R MAR 21 2000

SECTION

Compliance with ACT 345, P.A. 1990

APPROVED ON: 6-6-99-JK
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. A dot is marked in row 3, column B.

I, Huston K. Kennedy, in a field survey on April 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1.) 1973-Albright, PS #10057; LCRC L.6373, pg.870 - Fnd a 1/2" Re-rod
2.) 1992-Smith, PS #21582; LCRC L.12579, pg.773 - Fnd a 1/2" Re-rod
3.) 1973-Feldhauser Associates, Inc., Unrecorded Survey - Object found not stated, no witnesses
4.) 1976-Albright, PS #10057; Unrecorded Survey - Fnd 1/2" Re-rod, used same wit as 1973 LCRC
5.) 1983-Smith, PS #21582; Unrecorded Survey - Fnd 1/2" Re-rod, used same wit as 1973 LCRC
6.) 1987-E.E. Anderson & Associates; Unrecorded Survey - Object found not stated, no witnesses
7.) 1987-Scharl, PS #19843; Unrecorded Survey - Fnd 1/2" Re-rod, used same wit as 1973 LCRC
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 -



Witnesses from LCRC #1 were used to recover and verify the location of the found

I accepted the found as the best evidence of the original corner position.

FIELD MEASUREMENTS

B-3 to A-3
GLO = 30.41 chains or 2007.06 Ft.
1996.86 Ft. (GPS-MEA)

B-3 to C-3
GLO = 40 chains or 2640.00 Ft.
Sidwell E 1/2 Sec 7 (11-7) = 2642.45 Ft.
Sidwell SE 1/4 Sec 6 (11-6S) = 2625.60 Ft.
Unrecorded Survey by James Smith, PS #21582 dated 10/5/83 = 2640.53 Ft.
2640.25 Ft. (GPS-MEA)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
B-3 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
Due South 27.60' Set Mag Nail & Remon Washer West face 42" Oak
N41°E 47.85' Set Mag Nail & Remon Washer SE face 18" Oak
N16°E 34.75' Set Mag Nail & Remon Washer SE face 24" Oak
N54°W 57.40' Set Mag Nail & Remon Washer South face 38" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 6-1-99