

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

51118

LIBER 21118 PAGE 112
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/18/2000 10:02:41 A.M. RECEIPT# 139
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF

For corners in

Oakland
(County)

Located in: Highland Township
Corner Code #

1. Public Land Survey

T3N R7E B-7

2. Property Controlling in Section

S T R SURVEY &
S T R RE-MONUMENTATION
S T R
S T R MAR 21 2000

3. Miscellaneous Property in Sec.

4. Lot No. Recorded Plat SECTION
5. Private Claims

Compliance with ACT 345, P.A. 1990
APPROVED ON: 8-31-99 JA
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is present in row 7, column B.

I, Huston K. Kennedy, in a field survey on April 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: 1823GLO Wampler, D.S.; Set Post 10" White Oak S47 1/2 E 33 Links; 9" White Oak N19 W 29 Links

- 1.) 1990-Boss, PS #17022; Unrecorded Survey - Fnd a Concrete Monument
2.) 1991-McCoy, PS #21270; Unrecorded Survey - Object found not stated, no witnesses
3.) 1992-Kapelczak, PS #24598; Unrecorded Survey - Object found not stated, no witnesses
4.) 1992-Boss, PS #17022; Unrecorded Survey - Fnd Concrete Monument, used same wit as unrecorded Survey #1
5.) 1928-Baldwin, Unrecorded Survey - Object found not stated, no witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 4" diameter broken Concrete Monument with a fence extending to the North & South, also a chain link fence corner 32 feet to the South.

Witnesses from Unrecorded Survey #1 were used to recover and verify the location of the found 4" diameter broken Concrete Monument.

I accepted the found 4" diameter broken Concrete Monument as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

B-7 to C-7

GLO = 40 chain or 2640.00 Ft.
Sidwell E 1/2 Sec 19 (11-19) = 2635.97 Ft. 11
"DUNHAM LAKE HEIGHTS" + Parcels (Sec 18) = 2636.22 Ft.
Unrecorded Survey by Maurice E. Baldwin, PS #1298 dated 7/17/28 = 2634.21 Ft. (CAL)
Unrecorded Survey by Joseph C. Kapelczak, PS #24598 dated 1/28/92 = 2636.10 Ft.
Unrecorded Survey by Raymond J. McCoy, PS #21270 dated 4/11/91 = 2636.10 Ft.
Unrecorded Survey by Gary R. Boss, PS #17022 dated 5/25/90 = 2635.97 Ft.
2639.83 Ft. (GPS-MEA)

B-7 to A-7

GLO = 30.32 chains or 2001.12 Ft.
2003.51 Ft. (Calculated from "DUNHAM LAKES ESTATES NO. 1")
1984.35 Ft. (GPS-CAL M-7 to B-7)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: B-7 I replaced the found 4" diameter broken Concrete Monument with a new 4" diameter Concrete Monument. Rod 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
S77 E 10.32' Set Mag Nail & Remon Washer North face 12" Walnut
S87 W 15.13' Set Mag Nail & Remon Washer South face 22" Pine
S29 W 18.39' Set Mag Nail & Remon Washer SE face 32" Oak
S42 E 27.83' Set Mag Nail & Remon Washer SW face 11" Oak



The selected location is accepted by me and is generally accepted by Professional Surveyors as the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 2-10-2000