

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland
(County)

Located In: Highland Township Corner Code #

38626

LIBER 21077 PAGE 427
\$9.00 MISC RECORDING
\$2.00 REMUNERATION
02/08/2000 09:02:24 A.M. RECEIPT# 10181
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CABDELL, CLERK/REGISTER OF DEEDS

RECORDED
1999

REMOVED ON: 12-14-99 JL
OAKLAND COUNTY PERMANENT RECORDS
RECORDS GROUP COMMITTEE

Register of Deeds Stamp & File Number

1. Public Land Survey T3N R7E B9
 T R
 T R
 T R
 T R

2. Property Controlling In Section S T R
 S T R
 S T R

3. Miscellaneous Property In Sec. S T R
 S T R

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on October 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 15" Black Oak N07°W 17 Links; 15" Black Oak S58°W 22 Links
 1.) 1976-Hooth, PS #7968; LCRC L.6770, pg.841 & 842 - Set a Copperweld Rod stamped MDSH&T in a Monument Box
 2.) Kostecke, PS #12584; unrecorded Survey - Object found not stated, no witnesses
 3.) 1978-Kostecke, PS #12584; unrecorded Survey - Object found not stated, no witnesses
 4.) 1979-Kostecke & Associates, Inc.; unrecorded Survey - Object found not stated, no witnesses
 5.) 1980-Smith, PS #23518; unrecorded Survey - Fnd a Copperweld Rod in a Monument Box
 6.) 1987-Bonno, PS #32332; unrecorded Survey - Fnd a Monument Box and 1/2" Re-rod
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a Copperweld Rod w/cap in the existing centerline of East bound lan of M-59 Highway extending to the East & West, which has a bituminous surface, 60 feet East of the existing centerline of Center Lane Driv extending to the South, which has a bituminous surface

Witnesses from LCRC #1, unrecorded Survey #5 and local monumentation were used to recover and verify the location of th found Copperweld Rod w/cap.

I accepted the found Copperweld Rod w/cap as the best evidence of the original corner position.

Field measurements see back side

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 B-9 I replaced the found Copperweld Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped
 Remonumentation, PS #17623 in a new Monument Box
 N47°E 291.74' Set Mag Nail & Remon Washer NW face 6" Maple
 S52°W 104.71' Set Mag Nail & Remon Washer NW face Power Pole
 S24°E 50.17' Set Mag Nail & Remon Washer NE face Power Pole
 S63°E 188.83' Set Mag Nail & Remon Washer NE face Power Pole
 N03°W 199.00' Fnd 1/2" Iron Rod



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature] Date 12-16-99
Surveyor's Michigan License No. 17623

SURVEY &
RECORDS REGISTRATION

MAR 21 2008

SECTION

FIELD MEASUREMENTS BETWEEN

B-9 to A-9

GLO = 29.40 chains or 1940.40 Ft.
"VAN SCHOICKE SUBDIVISION" (Sec 19) = 1960.32 Ft.
M.DOT Right of Way Map = 1959.85 Ft.
1959.26 Ft. (GPS-MEA)

B-9 to C-9

GLO = 40 chains or 2640.00 Ft.
Sidwell E ½ Sec 19 (11-19) = 2647.99 Ft.
Unrecorded Survey by Richard L. Smith, PS #23518 dated 9/27/80 (Sec 30) = 2648.41 Ft.
M.DOT Right of Way Map = 2648.46 Ft.
2648.85 Ft. (GPS-MEA)