

LIBER 19872PG089
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland
 (County)

Located in: Highland Township Corner Code #

139677

1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.

T3N	R7E	C-1
T	R	
T	R	
T	R	
S	T	
S	T	
S	T	
S	T	

LIBER 19872 PAGE 89
 \$7.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 04/22/1999 07:54:23 A.M. RECEIPT# 22152
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 4-15-99 JS
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____ SECTION _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on March 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1815-1816-GLO Holmes, D.S.; Set Post 20" White Oak S11°E 40 Links; 10" White Oak S29°W 56 Links
- 1.) 1972-Albright, PS #10057; LCRC L.8002, Pg.510 - Fnd 3/4" Iron Bar
 - 2.) 1979-Finney, PS #15536; LCRC L.7580, Pg.809 - Fnd 1/2" Iron Rod
 - 3.) 1982-Oakland County Road Commission Unrecorded Witnesses - Fnd a Iron Pin
 - 4.) 1972-Albright, PS #10057; Unrecorded Survey - Fnd 1/2" Re-rod, used same wit as 1972 LCRC
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 5/8" Iron Rod in a Monument Box located 2.5 feet East of the existing centerline of Hickory Ridge Road extending to the North & South, which has a bituminous surface. An old tree-fence row extends to the East & West. Corner common to Sections 31 & 32, T4N, R7E, Rose Township (C-13) and is located 358.84 feet to the East. The corner as found is 1.60 feet South of the town line and was reset on the town line.

Witnesses from LCRC #1 were used to recover and verify the location of the found 5/8" Iron Rod in a Monument Box.
 I accepted the found 5/8" Iron Rod in a Monument Box as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

C-1 to B-1
 No GLO
 Unrecorded Survey by J. Albright, PS #10057 dated 2/4/72 = 2648.64 Ft.
 2648.26 Ft. (GPS-MEA)

C-1 to C-2
 GLO = 49.66 chains or 3277.56 Ft.
 No sidwell or plat distances
 3298.90 Ft. (GPS-MEA)
 3298.51 Ft. (GPS-MEA) Reset on the town line

C-1 to C-13
 GLO = 5.36 chains or 350.00 Ft.
 358.84 Ft. (m)

C-1 to D-1
 No GLO
 No sidwell or plat distances
 2709.38 Ft. (GPS-MEA)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 C-1 I set a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a new Monument Box on the town line
- | | |
|--|----------------------------------|
| Due East 49.35' Set Mag Nail & Remon Washer South face Power Pole | S87°W 35.33' found 1/2" Iron Rod |
| N18°E 98.05' Set Mag Nail & Remon Washer NW face 33" Walnut | N87°E 32.94' found 1/2" Iron Rod |
| N23°W 127.35' Set Mag Nail & Remon Washer NE face 16" Walnut | |
| S73°W 50.55' Set Mag Nail & Remon Washer South face Power Pole | |
| East 358.84' corner common to Sections 31 & 32, T4N, R7E, Rose Township (C-13) | |

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
 Surveyor's Michigan License No. 17623

Date 4-15-99