

SURVEY & REMONUMENTATION

MAY 24 2000

SECTION

LIBER 20934 262

457119

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 20934 PAGE 262
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
12/29/1999 02:45:18 P.M. RECEIPT# 110738
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

<u>Oakland</u> (County)	Located in: Highland Township	Corner Code # C-7
1. Public Land Survey	T3N T T T	R7E R R R
2. Property Controlling in Section	S S S	T T T
3. Miscellaneous Property in Sec.	S S	T T

ACT 345, P.A. 1990

RECORDED ON: 11-24-99 JK
OAKLAND COUNTY REMONUMENTATION
CLERK GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Huston K. Kennedy, in a field survey on April 27, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; Set Post 22" White Oak N38 1/2°E 57 Links; 27" White Oak S53 1/2°W 77 Links
- 1990-Newman, PS #24607; LCRC L.11604, Pg.647 - Fnd 1/2" Re-rod
 - 1928-Baldwin, PS #1298; Unrecorded Survey - Object found not stated, no witnesses
 - 1975-Kostecke, PS #12584; Unrecorded Survey - Fnd a Iron Rod, no witnesses
 - 1988-Newman, PS #24607; Unrecorded Survey - Fnd a 1/2" Re-rod, used same wit as 1990 LCRC
 - 1990-Boss, PS #17022; Unrecorded Survey - Fnd 1/2" Iron Rod
 - 1990-Kostecke, PS #12584; Unrecorded Survey - Fnd a Re-rod
 - 1991-McCoy, PS #21270; Unrecorded Survey - Object found not stated, no witnesses
 - 1991-Kostecke, PS #12584; Unrecorded Survey - Monument, no witnesses (Con't on back side)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. -- Kennedy, PS #17623 - Fnd a 1/2" Iron Rod in a Monument Box located in the existing centerline of Hickory Ridge Road extending to the North & South, which has a bituminous surface, also in the existing centerline of Wardlow Road extending to the East, which has a gravel surface, and a tree-fence row extending to the West.

Witnesses from LCRC #1 & Unrecorded Surveys #2, 3 & 9 were used to recover and verify the location of the found 1/2" Iron Rod in a Monument Box.

I accepted the found 1/2" Iron Rod in a Monument Box as the best evidence of the original corner position

Field measurements see back of LCRC

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-7 I replaced the found 1/2" Iron Rod with a 1/2" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a existing Monument Box
N38°E 58.10' Set Mag Nail & Remon Washer NW face Power Pole
S57°E 107.86' Set Mag Nail & Remon Washer SW face 8" Box Elder
N34°W 58.66' Set Mag Nail & Remon Washer NE face Power Pole
S47°W 47.82' Set Mag Nail & Remon Washer SE face 17" Box Elder



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 11-4-99